

AD-A103 938

NEW JERSEY DEPT OF ENVIRONMENTAL PROTECTION TRENTON --ETC F/G 13/13
NATIONAL DAM SAFETY PROGRAM, LAKE KALMIA DAM (NJ00166), DELAWARE--ETC(U)
AUG 81 W A GUINAN

DACW61-79-C-0011

UNCLASSIFIED

DAEN/NAP-53842/NJ00166-81/ NL

1 OF 1
AD-A
103 938

END
DATE
FILMED
10-81
DTIC

AD A103938



DELAWARE RIVER BASIN
TRIBUTARY TO PAULINS KILL,
WARREN COUNTY
NEW JERSEY

LAKE KALMIA DAM

NJ 00166

PHASE 1 INSPECTION REPORT
NATIONAL DAM SAFETY PROGRAM



APPROVED FOR PUBLIC RELEASE
DISTRIBUTION UNLIMITED.

DEPARTMENT OF THE ARMY

Philadelphia District
Corps of Engineers
Philadelphia, Pennsylvania

S

DTIC

FILED

SEP 9

REPT. NO: DAEN/NAP-53842/NJ00166-81/08

AUGUST 1981

81 9 08 039

DTIC FILE

REPORT DOCUMENTATION PAGE		READ INSTRUCTIONS BEFORE COMPLETING FORM
1. REPORT NUMBER DAEN/NAP-53842/NJ00166-81/08	2. GOVT ACCESSION NO. ADA103 938	3. RECIPIENT'S CATALOG NUMBER
4. TITLE (and Subtitle) Phase I Inspection Report National Dam Safety Program Lake Kalmia Dam (NJ00166), Warren County, New Jersey	5. TYPE OF REPORT & PERIOD COVERED FINAL	
7. AUTHOR(s) Guinan, Warren, P.E.	6. PERFORMING ORG. REPORT NUMBER B-111111111	
9. PERFORMING ORGANIZATION NAME AND ADDRESS Anderson-Nichols 150 Causeway St. Boston, MA 02114	8. CONTRACT OR GRANT NUMBER(s) DACW61-79-C-0011	
11. CONTROLLING OFFICE NAME AND ADDRESS NJ Department of Environmental Protection Division of Water Resources P.O. Box CNO29 Trenton, NJ 08625	10. PROGRAM ELEMENT, PROJECT, TASK AREA & WORK UNIT NUMBERS	
14. MONITORING AGENCY NAME & ADDRESS (if different from Controlling Office) U.S. Army Engineer District, Philadelphia Custom House, 2d & Chestnut Streets Philadelphia, PA 19106	12. REPORT DATE August, 1981	
	13. NUMBER OF PAGES 50	
	15. SECURITY CLASS. (of this report) Unclassified	
16. DISTRIBUTION STATEMENT (of this Report) Approved for public release; distribution unlimited. <i>Warren A. Guinan</i>		
17. DISTRIBUTION STATEMENT (of the abstract entered in Block 20, if different from Report)		
18. SUPPLEMENTARY NOTES Copies are obtainable from National Technical Information Service, Springfield, Virginia 22151.		
19. KEY WORDS (Continue on reverse side if necessary and identify by block number) Dams National Dam Safety Program Embankments Lake Kalmia Dam, N.J. Visual Inspection Erosion Structural Analysis Seepage Spillways		
20. ABSTRACT (Continue on reverse side if necessary and identify by block number) This report cites results of a technical investigation as to the dam's adequacy. The inspection and evaluation of the dam is as prescribed by the National Dam Inspection Act, Public Law 92-367. The technical investigation includes visual inspection, review of available design and construction records, and preliminary structural and hydraulic and hydrologic calculations, as applicable. An assessment of the dam's general condition is included in the report.		



IN REPLY REFER TO

NAPEN-N

DEPARTMENT OF THE ARMY
PHILADELPHIA DISTRICT, CORPS OF ENGINEERS
CUSTOM HOUSE-2 D & CHESTNUT STREETS
PHILADELPHIA, PENNSYLVANIA 19106

Honorable Brendan T. Byrne
Governor of New Jersey
Trenton, New Jersey 08621

31 AUG 1981

Accession For	
NTIS GRA&I	<input checked="" type="checkbox"/>
DTIC TAB	<input type="checkbox"/>
Unannounced	<input type="checkbox"/>
Justification	
By _____	
Distribution/	
Availability Codes	
Dist	Avail and/or Special
A	

Dear Governor Byrne:

Inclosed is the Phase I Inspection Report for Lake Kalmia Dam in Warren County, New Jersey which has been prepared under authorization of the Dam Inspection Act, Public Law 92-367. A brief assessment of the dam's condition is given in the front of the report.

Based on visual inspection, available records, calculations and past operational performance, Lake Kalmia Dam, initially listed as a high hazard potential structure but reduced to a low hazard potential structure as a result of this inspection, is judged to be in poor overall condition. Also, the dam's spillway is considered inadequate since 2 percent of the 100 year flood would overtop the dam. The low hazard potential classification means that in the event of failure of the dam, no loss of life and only minimal economic loss is expected. For the same reasons no further studies or increase of spillway capacity are recommended. To assure continued functioning of the dam and its impoundment, the following actions could be undertaken by the owner:

- a. Repair the depression and cracking of the concrete slab on the dam crest.
- b. Remove trees and their root systems from the crest and downstream slope of the dam.
- c. Take action to correct potential erosion and undermining of the downstream toe of the dam caused by the flow of water from seepage near the right abutment.
- d. Take action to correct seepage and wet, soft areas along the downstream toe of the spillway.



D

APPROVED FOR PUBLIC RELEASE;
DISTRIBUTION UNLIMITED.

NAPEN-N

Honorable Brendan T. Byrne

A copy of the report is being furnished to Mr. Dirk C. Hofman, New Jersey Department of Environmental Protection, the designated State Office contact for this program. Within five days of the date of this letter, a copy will also be sent to Congressman Courter of the Thirteenth District. Under the provision of the Freedom of Information Act, the inspection report will be subject to release by this office, upon request, five days after the date of this letter.

Additional copies of this report may be obtained from the National Technical Information Services (NTIS), Springfield, Virginia 22161 at a reasonable cost. Please allow four to six weeks from the date of this letter for NTIS to have copies of the report available.

An important aspect of the Dam Inspection Program will be the implementation of the recommendations made as a result of the inspection. We accordingly request that we be advised of proposed actions taken by the State to implement our recommendations.

Sincerely,



ROGER L. BALDWIN
Lieutenant Colonel, Corps of Engineers
Commander and District Engineer

Incl
As stated

Copies furnished:

Mr. Dirk C. Hofman, P.E., Deputy Director
Division of Water Resources
N.J. Dept. of Environmental Protection
P.O. Box CN029
Trenton, NJ 08625

Mr. John O'Dowd, Acting Chief
Bureau of Flood Plain Regulation
Division of Water Resources
N.J. Dept. of Environmental Protection
P.O. Box CN029
Trenton, NJ 08625

LAKE KALMIA DAM (NJ00166)


CORPS OF ENGINEERS ASSESSMENT OF GENERAL CONDITIONS

This dam was inspected on 22 April 1981 by Anderson-Nichols and Co. Inc., under contract to the State of New Jersey. The State, under agreement with the U.S. Army Engineer District, Philadelphia, had this inspection performed in accordance with the National Dam Inspection Act, Public Law 92-367.

Lake Kalmia Dam, initially listed as a high hazard potential structure but reduced to a low hazard potential structure as a result of this inspection, is judged to be in poor overall condition. Also, the dam's spillway is considered inadequate since 2 percent of the 100 year flood would overtop the dam. The low hazard potential classification means that in the event of failure of the dam, no loss of life and only minimal economic loss is expected. For the same reasons no further studies or increase of spillway capacity are recommended. To assure continued functioning of the dam and its impoundment, the following actions could be undertaken by the owner:

- a. Repair the depression and cracking of the concrete slab on the dam crest.
- b. Remove trees and their root systems from the crest and downstream slope of the dam.
- c. Take action to correct potential erosion and undermining of the downstream toe of the dam caused by the flow of water from seepage near the right abutment.
- d. Take action to correct seepage and wet, soft areas along the downstream toe of the spillway.

APPROVED:



ROGER L. BALDWIN

Lieutenant Colonel, Corps of Engineers
Commander and District Engineer

DATE:

31 Aug 81

PHASE I INSPECTION REPORT
NATIONAL DAM SAFETY PROGRAM

Name of Dam:	Lake Kalmia
Identification No.:	Fed ID No. NJ00166
State Located:	New Jersey
County Located:	Warren
Stream:	Tributary to Paulins Kill
River Basin:	Delaware
Date of Inspection	April 22, 1981

ASSESSMENT OF GENERAL CONDITIONS


Lake Kalmia Dam is 52 years old and in poor condition. It is small in size and should be downgraded to low hazard from its initial classification of high hazard. It is a 346-foot long earthen embankment with a concrete upstream face along most of its length. The dam has a hydraulic height of 6.6 feet. Its spillway is a broadcrested 4.3-foot wide weir passing flow through a flume 0.8-foot deep and 39.5 feet long across the dam crest. The low-level outlet is a valved 8-inch CIP. The soft, wet areas and seepage at the downstream toe of the dam near the right abutment are indicative of seepage through or under the dam. Trees growing on the dam crest and downstream slope and brush which eventually attains tree size may cause seepage and erosion problems. The flow of water along a portion of the toe of the dam from the seep near the right abutment could erode the toe of the embankment which could contribute to stability problems. Erosion and further deterioration of the downstream vertical, concrete-faced masonry wall (probably remnants of the original spillway) could contribute to stability problems, if not controlled. Cracks and spalling of the upstream, vertical concrete wall, if not repaired, could also contribute to stability problems. The depression and cracking of the concrete slab on the dam crest near the upstream face and left of the spillway flume may be indicative of internal erosion and should be corrected. The spillway capacity of 9.2 cfs at top of dam is 1.9 percent of the routed 100-year spillway design flood peak discharge of 487 cfs, and it is considered inadequate.

Lake Kalmia Dam does not now pose a potential hazard to loss of life and only minimal property damage could occur if it should be breached. However, should the owner wish to maintain the integrity of the embankment he should retain the services of a professional engineer, qualified in the design and construction of dams to accomplish the following in the near future: Investigate the cause of the depression and cracking of the concrete slab on the dam crest and design and oversee required corrective measures; design and oversee procedures for the removal of trees and their root systems from the crest and downstream slope of the dam; evaluate the potential for

erosion and undermining of the downstream toe of the dam caused by the flow of water from seepage near the right abutment; investigate the cause of seepage and wet, soft areas along the downstream toe of the spillway and design remedial measures; design or specify repairs for the vertical, concrete-faced masonry wall at the end of the spillway apron and to the right and left of the spillway; design and oversee the repairs to the deteriorated concrete wall on the upstream face; design and oversee repairs to restore the low-level outlet to operable condition; and investigate the adequacy of the spillway capacity and design and oversee remedial measures as needed.

It is further recommended that the owner accomplish the following tasks as a part of operating and maintenance procedures. In the near future: start a program of periodically checking the condition of the dam and monitoring the wet area along the toe of the downstream slope; remove trees and brush for a distance of 100 feet from the toe of the dam; clear trees and brush on either side of the spillway discharge channel for a distance of 100 feet from the spillway crest or to the property line whichever is the lesser; develop written operating procedures and a periodic maintenance plan to ensure the safety of the dam.

ANDERSON-NICHOLS & COMPANY, INC.



Warren A. Guinan, P.E.
Project Manager
New Jersey No. 16848



LAKE KALMIA DAM
OVERVIEW PHOTO

April 22, 1981

PREFACE

This report is prepared under guidance contained in the Recommended Guidelines for Safety Inspection of Dams, for Phase I Investigations. Copies of these guidelines may be obtained from the Office of Chief of Engineers, Washington, D.C., 20314. The purpose of a Phase I Investigation is to identify expeditiously those dams which may pose hazards to human life or property. The assessment of the general condition of the dam is based upon available data and visual inspections. Detailed investigation, and analyses involving topographic mapping, subsurface investigations, testing, and detailed computational evaluations are beyond the scope of a Phase I investigation; however, the investigation is intended to identify any need for such studies.

In reviewing this report, it should be realized that the reported condition of the dam is based on observations of field conditions at the time of inspection along with data available to the inspection team. It is important to note that the condition of a dam depends on numerous and constantly changing internal and external conditions, and is evolutionary in nature. It would be incorrect to assume that the present condition of the dam will continue to represent the condition of the dam at some point in the future. Only through continued care and inspection can there be any chance that unsafe conditions be detected.

Phase I Inspections are not intended to provide detailed hydrologic and hydraulic analyses. In accordance with the established Guidelines, the Spillway Test Flood is based on the estimated "Probable Maximum Flood" for the region (greatest reasonable possible storm runoff), or fractions thereof. The test flood provides a measure of relative spillway capacity and serves as an aid in determining the need for more detailed hydrologic and hydraulic studies, considering the size of the dam, its general condition and the downstream damage potential.

PHASE I INSPECTION REPORT
NATIONAL DAM SAFETY INSPECTION PROGRAM
LAKE KALMIA DAM
FED ID NO. #NJ00166

SECTION 1
PROJECT INFORMATION

1.1 General

a. Authority. Authority to perform the Phase I Safety Inspection of Lake Kalmia Dam was received from the State of New Jersey, Department of Environmental Protection, Division of Water Resources by letter dated 12 December 1980 under Basic Contract No. FPM-39, and Contract No. A01093 dated 10 October 1979. This Authority was given pursuant to the National Dam Inspection Act, Public Law 92-367 and by agreement between the State and the U.S. Army Engineers District, Philadelphia. The inspection discussed herein was performed by Anderson-Nichols & Company, Inc.

b. Purpose. The purpose of the Phase I Investigation is to develop an assessment of the general conditions with respect to the safety of Lake Kalmia Dam and appurtenances. Conclusions are based upon available data and visual inspection. The results of this study are used to determine any need for emergency measures and to conclude if additional studies, investigations, and analyses are necessary and warranted.

1.2 Project Description

a. Description of Dam and Appurtenances. Lake Kalmia Dam is a 346-foot long earth embankment with a concrete upstream face along most of its length. It has a hydraulic height of 6.6 feet, and a structural height of 7.5 feet. The embankment's width varies from 16 to 80 feet. The principal spillway is a 4.3 foot long broad-crested weir, about 0.8 feet below the low point of the dam. The 244-foot long concrete portion of the upstream slope is vertical. The rest of the upstream face and the downstream face vary in slope. Early plans show an 8-inch outlet pipe. The valve for this pipe is on the dam crest, but the outlet may not be in operating condition. About 400 feet east of the dam's left (east) abutment, a natural saddle would serve to carry some flow at high stages as an emergency spillway.

CONTENTS

PHASE I INSPECTION REPORT NATIONAL DAM SAFETY REPORT

LAKE KALMIA DAM FED ID NO. NJ00166

SECTION		<u>Page</u>
SECTION 1	PROJECT INFORMATION	
	1.1 <u>General</u>	1
	1.2 <u>Project Description</u>	1
	1.3 <u>Pertinent Data</u>	3
SECTION 2	ENGINEERING DATA	
	2.1 <u>Design</u>	5
	2.2 <u>Construction</u>	5
	2.3 <u>Operation</u>	5
	2.4 <u>Evaluation</u>	5
SECTION 3	VISUAL INSPECTION	6
SECTION 4	OPERATIONAL PROCEDURES	
	4.1 <u>Procedures</u>	7
	4.2 <u>Maintenance of Dam</u>	7
	4.3 <u>Maintenance of Operating Facilities</u>	7
	4.4 <u>Warning System</u>	7
	4.5 <u>Evaluation of Operational Adequacy</u>	7
SECTION 5	HYDRAULIC/HYDROLOGIC	8
SECTION 6	STRUCTURAL STABILITY	9
SECTION 7	ASSESSMENT, RECOMMENDATIONS/REMEDIAL MEASURES	
	7.1 <u>Assessment</u>	11
	7.2 <u>Recommendations/Remedial Measures</u>	11
FIGURES	1. Essential Project Features	
	2. Regional Vicinity Map	
APPENDICES	1. Engineering Data	
	2. Check List Visual Inspection	
	3. Photographs	
	4. Hydrologic Computations	
	5. HEC1 Output	
	6. References	

b. Location. The dam is located in Blairstown Township, Warren County, New Jersey on a tributary of Paulins Kill. The dam is at 40° 59.6' north latitude and 74° 58.0' west longitude on the Blairstown Quadrangle. The dam can be reached by taking State Route 521 North (Exit 12 off Interstate 80) for about 6 miles, to Mill Brook Road. The dam is approximately one mile down Mill Brook Road on the left hand side. A location map has been included as Figure 3.

c. Size Classification. Lake Kalmia Dam is classified as being small in size on the basis of storage at the dam crest of 92.8 acre-feet, which is less than 1000 acre-feet but more than 50 acre-feet, and on the basis of its structural height of 7.5 feet, which is less than 40 feet, in accordance with criteria given in the Recommended Guidelines for Safety Inspection of Dams.

d. Hazard Classification. The only structures along the stream downstream of Lake Kalmia Dam are the frame buildings of the old Girl Scout headquarters and seasonal cabins associated with a camp. The structures have been unoccupied for about 5 years and are scheduled to be torn down. Accordingly the hazard classification for this dam is low.

e. Ownership. Lake Kalmia Dam is owned by the Girl Scouts of Essex County, 120 Valley Road, Montclair, New Jersey 07042. The dam's caretaker, Art Hoehny, can be reached at (717) 828-2970.

f. Purpose. Lake Kalmia Dam was built for recreational purposes.

g. Design and Construction History. The dam was originally built in 1929. A plan and elevation of Lake Kalmia Dam entitled "Proposed Dam Reinforcement - Lake Kalmia - Blairstown, N.J., Mr. E. O. Ogur, Consulting Engineer, Newark, N.J." was available in the NJDEP files. The date on this plan is illegible, but believed to be dated October 25, 1935. Rebuilding was accomplished in 1936.

h. Normal Operational Procedure. No operational procedures for the dam were disclosed.

i. Site Geology. No site specific geologic information (such as borings) was available at the time the dam was inspected. Information derived from the Geological Map of New Jersey (Kummel and Johnson, 1912) indicates soils consist of till overlying bedrock.

The depth to bedrock at the dam site is unknown and outcrops were not observed during the dam inspection. The previous mentioned map indicates that bedrock in this area consists of massive to thin bedded limestone of Cambrian to Ordovician age. Based on information contained in New Jersey Department of Environmental Protection files, the area downstream contains sink holes (probably in the limestones).

1.3 Pertinent Data

a. Drainage Area

0.50 square miles (NJDEP records indicate 0.6 square miles).

b. Discharge at Damsite (cfs)

Maximum flood at damsite - unknown; caretaker indicates that dam was overtopped by 4 inches in the spring of 1981.

Total ungated spillway capacity at maximum pool elevation 411.1 (at top of dam) - 9.2.

c. Elevation (ft. above NGVD)

Top of dam - 411.1

Test flood surcharge (100-year storm) - 411.85

Recreational pool (at time of inspection) - 410.0

Spillway crest - 410.3

Streambed at centerline of spillway - 404.5

Maximum tailwater - 405.3 (estimated)

d. Reservoir (feet)

Length of maximum pool - 1200 (estimated)

Spillway crest - 1100 (estimated)

e. Storage (acre-feet)

Spillway crest - 77.0

Test flood surcharge (100-year storm) - 108

Top of dam - 92.8

f. Reservoir Surface (acres)

Top of dam - 20.3 (estimated)

Spillway crest - 19.2 (estimated)

g. Dam

Type - earthfill with concrete upstream face

Length - 346 feet

Height - 6.6 feet (hydraulic)

- 7.5 feet (structural)

Top Width - Varies from 16 to 80 feet

Side slopes - Upstream varies, vertical for much of
its length; downstream varies

Zoning - unknown

Impervious core - unknown

Cutoff - unknown

Grout curtain - unknown

h. Spillway

Type - Broad-crested concrete spillway flume 39.5 feet
in length

Length of weir - 4.3 feet

Crest elevation - 410.3' NGVD

Low level outlet - 8-inch valved CIP - may not be
operable

U/S Channel - Lake Kalmia

D/S Channel - Small unnamed stream (this stream
drains into a sink hole; no culvert is
present under road 0.2 mile downstream
of dam).

SECTION 2 ENGINEERING DATA

2.1 Design

No hydraulic, hydrologic, or other design engineering data were disclosed. The design plans for rebuilding the dam (1935) on file at NJDEP were in basic agreement with field observations.

2.2 Construction

Only correspondence concerning original construction of the Lake Kalmia Dam were disclosed. The rebuilding plan and profile (1935) was recovered from NJDEP files.

2.3 Operation

No data pertaining to the operation of the dam were found.

2.4 Evaluation

a. Availability. A search of the New Jersey Department of Environmental Protection files, and contact with community officials revealed a limited amount of information. All disclosed information was retrieved and is contained in Appendix 1.

b. Adequacy. The plans, supplemented by visual inspection, are deemed adequate to complete this Phase I inspection.

SECTION 3
VISUAL INSPECTION

3.1 Findings

a. Dam. Trees are growing on the crest of the dam, on the downstream slope, and in the area at the downstream toe of the dam. Cracked and spalled concrete was evident at several locations along the upstream vertical concrete wall.

Some seepage is discharging at the toe of the dam near the contact with the right abutment. The seepage is clear with no evidence of suspended fines. This seepage flows along the downstream toe until it reaches a large wet swampy area to the right of the spillway channel. The area at the downstream toe is generally wet and soft for its entire length, and contains extensive wetland vegetation.

A partially deteriorated concrete faced masonry stone wall, approximately 2 to 3 ft. high, was exposed to the right and left of the spillway for a distance of approximately 20 to 40 ft. The concrete faced wall grades into a series of large stones and boulders which have been placed along the toe.

A depression was observed in the crest of dam near the upstream face adjacent to the left side of the spillway flume. The concrete slab covering the crest is cracked and settled in this area.

b. Appurtenant Structures. Erosion has occurred on the downstream slope of the embankment adjacent to both spillway wingwalls. Extensive erosion has developed at the vertical masonry and concrete wall at the end of the spillway flume which was partially obscured owing to water flowing from the spillway flume during the site visit. The low-level outlet and gate valve were not visible at the time of inspection. (The outlet is reported to be an 8-inch CIP.) A vertical 12-inch CMP pipe stand on the dam crest apparently houses the valve stem.

c. Reservoir Area. The watershed above the lake is gently to moderately sloping and wooded. The reservoir slopes appear to be stable. No evidence of significant sedimentation was observed.

d. Downstream Channel. The channel downstream from the spillway is poorly defined and meanders past the large swampy area downstream from the dam. Some trees are growing on the banks of the channel downstream of the spillway. As no culvert could be found under the road 0.2 miles downstream, channel discharges may as yet be draining into the old sink hole mentioned in Section 1.2.h.

SECTION 4
OPERATIONAL PROCEDURES

4.1 Procedures

No formal operating procedures were revealed.

4.2 Maintenance of Dam

No formal maintenance procedures for the dam were found.

4.3 Maintenance of Operating Facilities

No formal maintenance procedures for the operating facilities were discovered.

4.4 Warning System

No description of any warning system was found.

4.5 Evaluation of Operational Adequacy

Because of the lack of operation and maintenance procedures, the remedial measures described in Section 7.2 should be implemented as described.

SECTION 5 HYDROLOGIC/HYDRAULIC

5.1 Evaluation of Features

a. Design Data. Because no original hydrologic/hydraulic design data were revealed, an evaluation of such data could not be performed.

b. Experience Data. No experience data were found. The caretaker, by phone, recently stated that the dam was overtopped by 4 inches in the spring of 1981 (probably subsequent to the site inspection).

c. Visual Inspection. The spillway for Lake Kalmia Dam consists of a 4.3 foot long concrete broad-crested weir discharging into a 39.5 foot long by 0.8 foot deep flume. No visual evidence was found of damage to the structure caused by overtopping. At the time of inspection, approximately 0.1 foot of water was flowing over the spillway crest.

d. Lake Kalmia Dam Overtopping Potential. The hydraulic/hydrologic evaluation for the dam is based on a selected Spillway Design Flood (SDF) equal to the 100-year flood in accordance with the range of test floods given in the evaluation guidelines, for dams classified as low hazard and small in size. The 100-year flood was determined by applying the 100-year 2-hour rainfall hyetograph to the SCS dimensionless unit hydrograph for the drainage area. Hydrologic computation are given in Appendices 4 and 5. The peak 100-year outflow from Lake Kalmia is 487 cfs.

The minimum elevation of the dam allows 0.8 foot of flow over the spillway crest before overtopping occurs. Under this head the spillway capacity is 9.2 cfs, which is about 1.9 percent of the selected SDF. Thus the spillway capacity is inadequate.

Under test flood conditions the natural saddle 400 feet east of the dam, which might serve as an emergency spillway would convey 96 cfs, with 26 cfs going over the spillway and 372 cfs over the dam crest. The elevation of the natural saddle is higher than the dam crest, so it does not increase project capacity at the top of the dam.

e. Drawdown. If the 8-inch cast iron pipe shown on the plans for Lake Kalmia Dam could be operated, it would draw Lake Kalmia down in 15 days assuming no inflow. This is considered marginal for draining the reservoir under emergency conditions; but adequate, considering the small drainage area.

SECTION 6 STRUCTURAL STABILITY

6.1 Evaluation of Structural Stability

The soft, wet area and seepage at the downstream toe of the dam near the right abutment are indicative of seepage either through or under the dam which, if not properly controlled, could lead to failure of the dam by piping or sloughing of the downstream slope. The flow of water along a portion of the toe of the dam from the seep near the right abutment could erode the toe of the embankment which would contribute to stability problems. Trees growing on the crest and downstream slope and brush which eventually attain tree size may cause seepage and erosion problems. This is especially true if a tree blows over and pulls out its roots, or if a tree dies or is cut and its roots rot. Erosion and further deterioration of the downstream, vertical, concrete-faced masonry wall (probably remnants of the original spillway) could contribute to stability problems in the embankment, if not properly controlled. Cracks and spalling of the upstream, vertical, concrete wall, if not repaired, could also contribute to stability problems.

The depression and cracking of the concrete slab on the dam crest near the upstream face and left side of the spillway flume may be indicative of internal erosion and should be corrected.

6.2 Design and Construction Data

No design or construction data pertinent to the structural stability of the dam are available.

6.3 Operating Records

No operating records pertinent to the structural stability of the dam are available.

6.4 Post-Construction Changes

A plan showing the rebuilding, accomplished in 1936, shows the upstream concrete wall and spillway to be as noted in the inspection (See Appendix 1). State of New Jersey records (see also Appendix 1) reflect that the saddle, 400 feet left of the dam, contained a second concrete spillway that would have been the principal spillway as its invert was one-half foot lower than that of the flume spillway at the dam. No evidence of the concrete work in this area was observed.

6.5 Seismic Stability. This dam is in Seismic Zone 1. According to the Recommended Guidelines, dams located in Seismic Zone 1 "may be assumed to present no hazard from earthquake, provided static stability conditions are satisfied and conventional safety margins exist." None of the visual observations made during the inspection are conclusively indicative of unstable slopes. However, because no data are available concerning the engineering properties of the embankment and foundation materials for this dam, or the condition of the base of the dam, it is not possible to make an engineering evaluation of the stability of the slopes or the factor of safety under static conditions.

SECTION 7
ASSESSMENT, RECOMMENDATIONS/REMEDIAL MEASURES

7.1 Dam Assessment

a. Condition. Lake Kalmia Dam is 52 years old and is in poor condition.

b. Adequacy of Information. The information available is such that the assessment of the dam must be based primarily on the results of the visual inspection.

c. Urgency. Because the dam poses no hazard to life and little hazard to property there is little urgency to implement the recommendations in Section 7.2 based on safety considerations. Should the owner wish to maintain the dam embankment the recommendations should be implemented as prescribed.

d. Necessity for Additional Data/Evaluation. The information available from the visual inspection is adequate to identify the potential problems which are listed in 7.2.a. These problems require the attention of a professional engineer who will have to make additional engineering studies to design or specify remedial measures to rectify the problems. If left unattended, the problems could lead to failure of the dam.

7.2 Recommendatons/Remedial Measures

a. Recommendations. The owner should retain a professional engineer qualified in the design and construction of dams to accomplish the following in the near future:


- (1) Investigate the cause of the depression and cracking of the concrete slab on the dam crest and design and oversee required corrective measures.
- (2) Design and oversee procedures for the removal of trees and their root systems from the crest and downstream slope of the dam.
- (3) Evaluate the potential for erosion and undermining of the downstream toe of the dam caused by the flow of water from seepage near the right abutment.
- (4) Investigate the cause of seepage and wet, soft areas along the downstream toe of the spillway and design remedial measures.

- (5) Design or specify repairs for the vertical, concrete-faced masonry wall at the end of the spillway apron and to the right and left of the spillway.
- (6) Design and oversee the repairs to the deteriorated concrete wall on the upstream face.
- (7) Design and oversee repairs to restore the low-level outlet to operable condition.
- (8) Investigate the adequacy of the spillway capacity and design and oversee remedial measures as needed.

b. Alternatives. If the recreational aspects of this dam and reservoir are considered essential, no alternative is recommended; however, if considered non-essential, the dam could be breached and the reservoir returned to the Lake Kalmia original state of a small springfed lake.


c. Operating and Maintenance Procedures. The owner should accomplish the following items in the near future:

- (1) Start a program of periodically checking the condition of the dam and monitoring the wet area along the toe of the downstream slope.
- (2) Remove trees and brush for a distance of 25 feet downstream from the toe of the dam or to the property line whichever is less.
- (3) Clear trees and brush on either side of the spillway discharge channel for a distance of 100 feet from the spillway crest or to the property line whichever is less.
- (4) Develop written operating procedures and a periodic maintenance plan to ensure the safety of the dam.



Anderson-Nichols & Co., Inc.		U.S. ARMY ENGINEER DIST PHILADELPHIA	
BOSTON		CORPS OF ENGINEERS	
MASSACHUSETTS		PHILADELPHIA, PA.	
NATIONAL PROGRAM OF INSPECTION OF NON-FED. DAMS			
LAKE KALMIA DAM			
PLAN			
TRIB. TO PAULINS KILL		NEW JERSEY	
		SCALE: NOT TO SCALE	
		DATE:	

FIGURE -1



Anderson-Nichols & Co., Inc.		U.S. ARMY ENGINEER DIST. PHILADELPHIA	
BOSTON		CORPS OF ENGINEERS	
MASSACHUSETTS		PHILADELPHIA, PA	
NATIONAL PROGRAM OF INSPECTION OF NON-FED DAMS			
LAKE KALMIA DAM			
ELEVATION			
TRIB. TO PAULINS KILL		NEW JERSEY	
		SCALE: NOT TO SCALE	
		DATE:	

FIGURE 5



SCALE IN MILES



MAP BASED ON STATE OF NEW JERSEY
OFFICIAL MAP & GUIDE.

Anderson-Nichols & Co., Inc.		U.S. ARMY ENGINEER DIST. PHILADELPHIA	
BOSTON		MASSACHUSETTS	
CORPS OF ENGINEERS PHILADELPHIA, PA.			
NATIONAL PROGRAM OF INSPECTION OF NON-FED. DAMS			
LAKE KALMIA DAM LOCATION MAP			
TRIB. TO PAULINS KILL		NEW JERSEY	
		SCALE: 1" = 4 Miles Approx.	
		DATE:	

APPENDIX 1

ENGINEERING DATA

LAKE KALMIA DAM

PATRICK

DAMS IN NEW JERSEY—REFERENCE DATA

Name of Owner: Newark City Schools NO. 21-30
 Name of Dam: Lake Katella Address: 901 Broad Street, Newark, N.J.
 COUNTY: Essex Location: 21.53.1.3.8
 CONSTRUCTION: Dam Rebuilt 1935-36 By whom: Longmire, Inc.
 Stream: Small Branch Tributary to: Fall Brook
 DRAINAGE BASIN: Area: 0.35 sq. mi. Description: Rollins, 1/2 wooded.
 Description of valley below dam: Meandering
 DAMAGE FROM FAILURE: Probable: None
 Previous (date):
 Purpose: Recreation Type: Earth, when built, reinforced concrete
 Foundation:
 Length: 240 ft. Max. height: 10 ft. Max. width of base: 100 ft.
 Upstream slope: Vertical Downstream slope: 1:1 Volume: cu. yd.
 SPILLWAY: Type: Concrete, notched Length: 100 ft.
 Depth below top of dam: 2' and 3.5' ft. Capacity: 50000 cu. ft. per sq. ft.
 RESERVOIR: Capacity: min. gate area: ft.
 Outlet: 1 - 18" C.I. Pipe with gate valve in manhole.
 Remarks: Spillway 1) Concrete brought on dam fill, 2) 1.5' deep, 3) concrete notch in middle of spillway, 4) 1.0' freeboard.
 Sources of data: Inspection and drawing filed 10/11/35 Date: 11/1/35


10/31/35
HJC
B

ham near Plainstown -
on very small brook - Reported by
~~person~~ person - with captioned
Newark Girl Scout Council

Mrs. Tom Vance

901 Broad St.

Newark



E. Ogur 446 N 9th St
E. Orange

P. E. House of
Leroy - House Line
336 Pleasant Ave
Princeton N.J.

Essex 2-6118

W. H. H. Co.
Newark Girl Scout Dam
Dam # 21-22
Fairfield

October 31, 1935.

Mr. P. G. Hasse,
336 Stuyvesant Avenue,
Irvington, N. J.

Dear Sir:

With regard to the repair of the Newark Girl Scout dam at Lake Kalmir near Blairstown, New Jersey, I wish to advise that after conversation with Mr. John Quigley, game warden residing in Blairstown, we were able to confirm your statement that this lake is spring fed and is not on a stream of any size. Under the circumstances, no formal permit is necessary from this Commission to repair the structure in accordance with the drawings prepared by E. Ogur, Consulting Engineer, Newark, dated October 25, 1935.

We are returning herewith the specification, but are retaining the drawing for our files.

Yours very truly,

H. T. Critchlow
Division Engineer.

Report on Dam Inspection

NEWARK GIRL SCOUT DAM

Dam No. 21 - 30.

Location 21.43.13.8.

At the request of Mr. Edward L. Lanterman, Engineer, inspection of this dam was made on January 14, 1930 in company with Mr. Lanterman.

Since the inspection of October 15, 1929 additional fill has been made on the top and the downstream slope of the dam, erosion of the earth fill has been stopped and a concrete notch spillway has been built in a natural saddle 500 feet to left of dam.

The additional fill on downstream slope of dam should be completed to the left end of embankment reducing the slope from 1 to 1 to about 1-1/2 to 1.

The spillway consists of a concrete wall with its top at the same elevation as the top of the dam and two openings each 2 feet deep and 12 feet long. With 1 foot freeboard the spillway capacity is 400 sec. ft. per sq. mi. and with the top of dam avash 1130 sec. ft. per sq. mi. From the spillway notch a small ditch has been dug around the back of the knoll to a limestone sink hole in the meadow below the dam. This sink hole is reported to have taken the stream flow before the dam was built. The ditch appears too small to carry the maximum spillway discharge but overflow from it will probably be infrequent and no damage is likely to be done by the overflow spreading out on the meadow below. A pile of clay which lies across the upstream side of the spillway should be removed.

Water in the pond stood 2 feet below the spillway crest.

The spillway capacity is sufficient to care for the probable maximum flood flow and the slopes of the earth embankment, though steeper than usually approved by the Commission's engineers are considered sufficient in view of the clay of which the banks are made and the absence of apparent damage should the dam fail by slumping of the embankment.

When the above mentioned work has been done, namely the completion of the additional fill on downstream slope and removal of clay bank in front of spillway, the dam may be considered satisfactory.



John N. Brooks,
Assistant Division Engineer.

Trenton, N. J.,
January 15, 1930.

Copy to Mr Hamilton

COMMISSIONERS

WILLARD I. HAMILTON, CHAIRMAN
NEWARK

F. MORSE ARCHER
CAMDEN

CORNELIUS DOREMUS
RIDGEWOOD

MAX GROSSMAN
ATLANTIC CITY

THURLOW G. NELSON
HIGHLAND PARK

HENRY G. PARKER
NEW BRUNSWICK

OWEN J. PRIOR
TRENTON



MORRIS R. SHERRERD
CHIEF ENGINEER

GEORGE S. BURGESS
SECRETARY
605 BROAD STREET
NEWARK, N. J.

STATE OF NEW JERSEY
STATE WATER POLICY COMMISSION

December 31, 1929. **RECEIVED**

Mr. H. T. Critchlow, Division Engineer,
State Water Policy Commission,
Trenton, N. J.

JAN 2 1930
STATE WATER POLIC
COMMISSION

Dear Mr. Critchlow:

In reply to yours of the 30th, enclosing copy of letter written to Mr. Lanterman, I quite agree with the practice followed, and since I am interested in the Girl Scouts organization, authorized the above to apply for the inspection merely in order to see that proper report of the completion of the work was made.

The precautions taken at my direction when the new dam was built represented a substantially greater margin of safety than required by law. One of Mr. Brooks' inspections was rendered necessary because he failed to get in touch with Mr. Lanterman as had been suggested, and either went alone or, as was rumored, perhaps inaccurately, with a contractor who had failed to secure some work. The net result was that he gained an erroneous impression, which was later corrected.

Yours sincerely,

Willard I. Hamilton
Chairman.

Trenton Office.

December 30, 1929.

Mr. Willard I. Hamilton, Chairman
State Water Policy Commission,
605 Broad Street,
Newark, N. J.

Dear Mr. Hamilton:-

I am enclosing for your information copy of my letter of even date herewith, to Mr. Edward L. Lanterman, in regard to inspection of the Newark Girl Scout dam near Blairstown.

This dam was inspected twice during last summer, and I am satisfied that it is in satisfactory condition for the winter. I doubt if any satisfactory inspection could be made at the present time.

Yours very truly,

H. T. Critchlow,
Division Engineer

JNB:121B

Fish Dam - ~~Swamp~~ Co.
Warren

RECEIVED

NOV 14 1929

STATE WATER POLICY
COMMISSION

Plaistown Nov 13 1929

Mr John Brooks
Dear Mr Brooks

Mr J. M. Crouse Contractor
is now putting the stone on the Dam known as
Newark Hill south of Plaistown nearly finished
I wish you would drop around and look it over
so we can finish it up to your satisfaction

Sincerely

Edward L. Lauterman

P.S. If you have a chance to let me know when
you will be up I will be glad to see you

Edward L. Lauterman
Blauvelt New Jersey

RECEIVED

SEP 28 1929

STATE WATER POLICY
COMMISSION

Mr John W. Brooks,
Hydraulic Engineer,
State Water Policy Commission,
State House Annex,
Trenton N.J.

September 26-1929

Dear Mr Brooks:

The improvements at the Newark Girl
Scouts' Camp at Blairstown, N.J. started in November, 1928.
Since receiving your letter I have made a survey of the
water shed at the lake and find the same to be about
One hundred acres.

There was no intention whatever of with holding an
application for permission to build the Dam at the
Girl Scouts' Camp, if it were necessary.

If you think it necessary, we can file an
Application now and send you the details, maps, etc.
but before doing so, think you should visit me
on the property and make a complete in-
spection with me. You will recall my earlier
invitation to do so when we met at Mountain
Lake at Mr. Folger's proposed dam.

(2)

However, I have been informed that you did inspect the site of the new Dam with someone else. Perhaps you were not aware of the provision we are making for an overflow or spillway at another part of the Lake.

You will be interested to know that my instructions from the Trustees of the Camp were to make the Core wall so strong as to be beyond the possibility of criticism. The width of the base and of the Core and the strength of the mixture are evidence of this fact.

The Core is two feet wide at the base and tapers to one foot at the top.

If you still think a formal application is necessary, Please advise me when you can meet me in Blairtown.

Yours very truly,
Edward L. Lantzman

SEP 10 929

SEP 10 1929
COMM. ON

Blairtown Sept-9-1929

Mr John W. Brooks

Dear Sir:

Your letter of the 6th
received as to the questions you ask
I have forwarded your letter to Mr Willard
Hamilton of Newark to answer same
The Dam is not finished yet,

and any suggestions you may make or
offer in any way will be gladly received
and I will mail them to Mr Hamilton.

Awaiting your reply

Remain Yours truly

Edward L. Lauterbach

PS Sorry I did not see you while you was
here

Report on Dam Inspection.

NEWARK GIRL SCOUTS

Dam No. ²¹⁻³⁰~~21-30~~

Location 21.43.1.3.8.

This dam was built during the spring of 1929 under the direction of Mr. Edward L. Lanterman of Blairstown, without permit.

The structure is an earth dam with concrete core wall, 250 feet long and with a maximum ~~pipe~~ 11 feet ~~long~~. The top width is 6 feet and the side slope 1:1. height of

The fill has been made of gravel without compacting and has been badly washed at the left end by flood water from a nearby road. The fill shows marked settlement throughout the length of the dam.

There is ¹⁻⁸~~1-8~~ inch cast iron blow-off pipe with gate valve ⁱⁿ~~and~~ manhole.


The dam has no spillway.

The water shed measures on the map 0.6 square mile. However, the small stream on which this dam has been placed formerly lost itself in a meadow below the dam site and there is no Culvert beneath the highway 0.2 mile below the dam.

It does not appear probably that the dam will ever be overtopped.

There was no water in the pond.

Trenton, N.J.,
September 6, 1929.


John N. Brooks,
Hydraulic Engineer.

Darius-Nansen Co

Trenton Office.

September 6th, 1929.

Mr. Ed. L. Lanterman,
Blairstown, N. J.

Dear Mr. Lanterman:-

We made an inspection this morning of the dam which you built for the Newark Girl Scouts about 1-1/2 mile northwest of Blairstown.

The drainage area tributary on this dam as measured on the State map is 0.6 square mile and the dam is 11 feet high.

Therefore, under the old law which was in force at the time this dam was built you should have made application to the proper State Authority for approval of your plans.

You will kindly be so good as to inform this office why the dam was built without the approval of plans.

Yours very truly,

STATE WATER POLICY COMMISSION.

John H. Brooks,
Hydraulic Engineer.

JNB:MHB

RECEIVED

AUG 5 1929

STATE WATER POLICE
COMMISSION

Plain town Aug 2^d 1929

Mr John N. Brooke

Dear Sir

Aug 5 1929 JNB
Your letter of July

31 st- received

I have looked on the enclosed
map you sent me the Place where the
Girls Scouts of Newark have built a new
Dam; This Place is simply a Spring run
feeding this place for the Girls & down in
This Spring run emptied into a Sink Hole
Just below the Dam and then disappeared
Any time you come up will show it to
you

As to the Springdale alterations that
Mr N.H. Hart runs there I do not know
what he intends to do as he has never told
me I have asked him several times but no
definite reply I ^{will} stir him up again shortly
then I will write you as soon as I can get

Something Tanagibable to write you
That place would make a fine Lake
if he decides to go ahead with it—

Yours truly
Edward L. Lamm

Did Mr. Folkner write you any thing
in regard to a Spring run he proposes to
dam up to make a fish Pond with dirt
just south of Mountain Lake formerly Queens Pond
I think he better build a concrete one dam
as he has a large water shed behind him
When he writes you, I will leave it all to your
judgement to tell him what to expect

APPENDIX 2

CHECK LIST

VISUAL INSPECTION

LAKE KALMIA DAM

Check List
Visual Inspection
Phase 1

Name Dam Lake Kalmia County Warren State NJ(00166) Coordinators NJDEP
 Date(s) Inspection 2/18/81 4/22/81 Weather' Warm, Sunny Clear Temperature 40° 65°
 Pool Elevation at Time of Inspection 410.3'+ NGVD Tailwater at Time of Inspection 405' NGVD

Inspection Personnel:

<u>K. Stuart</u>	<u>W. Guinan</u>
<u>D. Deane</u>	<u>S. Gilman</u>
<u></u>	<u>R. Murdock</u>

F.D.Deane/S.Gilman/R.Murdock Recorder

Ms. Marjorie Vance, representing the Girl Scouts of Essex County, was present during the April inspection.

UNGATED SPILLWAY

VISUAL EXAMINATION OF	OBSERVATIONS	REMARKS OR RECOMMENDATIONS
CONCRETE WEIR	<p>U/s face of dam is badly spalled and cracked. One section near right end is eroded in a "V" form approximately 8" deep - Reinforcing bars are showing. Concrete slabs on top are cracked and disjointed.</p> <p>Stop log slots approximately 1 foot downstream from inlet.</p>	<p>Repair deteriorated, cracked spalled concrete.</p>
APPROACH CHANNEL	<p>Clear and unobstructed;</p>	
DISCHARGE CHANNEL	<p>D/s face is eroded and spalled. D/s concrete masonry walls on either side of spillway channel are badly spalled and cracked.</p> <p>Trash and other debris at toe of spillway, including channel drain. Extensive vegetation, trees & debris, downstream from spillway apron. Drop-off chute spillway severely eroded.</p>	<p>Repair deteriorated concrete.</p> <p>Remove trash and debris. Clear vegetation.</p>

BRIDGE AND PIERS
OVER SPILLWAY

EMBANKMENT

VISUAL EXAMINATION OF	OBSERVATIONS	REMARKS OR RECOMMENDATIONS
SURFACE CRACKS	None	
UNUSUAL MOVEMENT OR CRACKING AT OR BEYOND THE TOE	None	
SLOUGHING OR EROSION OF EMBANKMENT AND ABUTMENT SLOPES	Erosion and sloughing on downstream slope. Trees up to 14 inches in diameter on slope.	Under qualified supervision, remove the trees and their roots.
VERTICAL AND HORIZONTAL ALIGNMENT OF THE CREST	Good	
RIPRAP FAILURES	No rip-rap.	

EMBANKMENT

VISUAL EXAMINATION OF	OBSERVATIONS	REMARKS OR RECOMMENDATIONS
RAILINGS	None	
JUNCTION OF EMBANKMENT AND ABUTMENT, SPILLWAY AND DAM	Erosion of both sides of spillway structure.	Repair eroded area.
ANY NOTICEABLE SEEPAGE	Seepage at toe of slope near junction with right abutment. Majority of area at toe of slope is wet and soggy.	Investigate seepage and correct problem.
STAFF GAGE AND RECORDER	None observed.	
DRAINS	None observed.	

OUTLET WORKS

VISUAL EXAMINATION OF	OBSERVATIONS	REMARKS OR RECOMMENDATIONS
CRACKING AND SPALLING OF CONCRETE SURFACES IN OUTLET CONDUIT	Could not observe either end of conduit.	
INTAKE STRUCTURE	Not observable.	
OUTLET PIPE	Not observed - d/s end covered with debris.	Clear debris.
OUTLET CHANNEL	Well-defined flat slope through open area with a few trees (cedar).	
EMERGENCY GATE	CMP access to valve filled with trash. Last operation unknown. Could not determine valve size.	

RESERVOIR

VISUAL EXAMINATION OF	OBSERVATIONS	REMARKS OR RECOMMENDATIONS
-----------------------	--------------	----------------------------

SLOPES

Gradual to moderately sloped,
wooded and some open fields.

SEDIMENTATION

No noticeable sedimentation
was observed.

DOWNSTREAM CHANNEL

VISUAL EXAMINATION OF	OBSERVATIONS	REMARKS OR RECOMMENDATIONS
CONDITION (OBSTRUCTIONS, DEBRIS, ETC.)	Trash and debris at spillway drop-off.	(See description of ungated spillway channel)
SLOPES	Flat	
APPROXIMATE NO. OF HOMES AND POPULATION	Three old former camp cabins to be razed - no occupants.	

CHECK LIST
ENGINEERING DATA
DESIGN, CONSTRUCTION, OPERATION

ITEM	REMARKS
PLAN OF DAM	None found. Information is available on the Proposed Dam Reinforcement Plan on file at the New Jersey Department of Environmental Protection, Prospect Street, Trenton, New Jersey 08625
REGIONAL VICINITY MAP	Prepared for this report
CONSTRUCTION HISTORY	Some information available in NJDEP files. Legible sheets are included in Appendix 1, ENGINEERING AND EXPERIENCE DATA.
TYPICAL SECTIONS OF DAM	Available from plan mentioned above
HYDROLOGIC/HYDRAULIC DATA	None found
OUTLETS - PLAN	None found
- DETAILS	8" C.I. Pipe with gate valve in manhole
- CONSTRAINTS	None found
- DISCHARGE RATINGS	None found
RAINFALL/RESERVOIR RECORDS	None found

ITEM	REMARKS
DESIGN REPORTS	None found
GEOLOGY REPORTS	None found
DESIGN COMPUTATIONS HYDROLOGY & HYDRAULICS DAM STABILITY SEEPAGE STUDIES	None found
MATERIALS INVESTIGATIONS BORING RECORDS LABORATORY FIELD	None found
POST-CONSTRUCTION SURVEYS OF DAM	See PLAN OF DAM on previous page
BORROW SOURCES	Unknown

ITEM	REMARKS
MONITORING SYSTEMS	None
MODIFICATIONS	Reinforcement. See PLAN OF DAM
HIGH POOL RECORDS	None found
POST CONSTRUCTION ENGINEERING STUDIES AND REPORTS	Some information available in NJDEP files. Legible sheets are included in Appendix 1, ENGINEERING AND EXPERIENCE DATA.
PRIOR ACCIDENTS OR FAILURE OF DAM DESCRIPTION REPORTS	Unknown
MAINTENANCE OPERATION RECORDS	None found

ITEMS	REMARKS
SPILLWAY PLAN	None found
SECTIONS	
DETAILS	
OPERATING EQUIPMENT PLANS & DETAILS	None found

CHECK LIST
HYDROLOGIC AND HYDRAULIC DATA
ENGINEERING DATA

DRAINAGE AREA CHARACTERISTICS: 0.50 square miles fields and woods
(50 percent each)

ELEVATION TOP NORMAL POOL (STORAGE CAPACITY): 410.3' NGVD (77 ac-ft)

ELEVATION TOP FLOOD CONTROL POOL (STORAGE CAPACITY: Not applicable

ELEVATION MAXIMUM TEST FLOOD POOL: 411.8' NGVD

ELEVATION TOP DAM: 411.1' NGVD (92.8 acre-feet)

SPILLWAY_CREST: Broad-crested

a. Elevation 410.3' NGVD upstream invert

b. Type Rectangular Flume

c. Width 4.3 feet (flume)

d. Length 39.5 feet (flume)

e. Location Spillover Center of dam

f. Number and Type of Gates None (stop log slots present)

OUTLET WORKS: One 8-inch pipe with valve (may not be operable)

a. Type Presumed to be cast iron pipe

b. Location Just left (east) of spillway

c. Entrance Invert 404' NGVD (estimated)

d. Exit Inverts 404' NGVD (estimated)

HYDROMETEOROLOGICAL GAGES: None

MAXIMUM NON-DAMAGING DISCHARGE: 9.2 cfs

APPENDIX 3

PHOTOGRAPHS

LAKE KALMIA DAM



April 22, 1981

Dam crest, note settlement and cracking of concrete adjacent to iron diving platform.



April 22, 1981

Downstream spillway channel below spillway apron.



April 22, 1981

Downstream end of spillway - note vertical drop of water.



February 18, 1981

Spillway exit - note debris at dropoff. The end is beginning to get undermined.




April 21, 1981

Saddle about 400 feet east of dam that probably would serve as emergency spillway. Looking at upstream face from west side of bay.




April 22, 1981

Settlement and cracked area under slab at spillway inlet at left training wall near diving board frame. Note training walls notched for stoplog.



April 22, 1981

Spalled concrete upstream wall in first dogleg
to left of spillway.



April 22, 1981

Spalled concrete upstream wall.



April 22, 1981

Erosion and deterioration of masonry wall at downstream face of dam, right (west) of spillway.



April 22, 1981

Erosion adjacent to left spillway wall.



April 12, 1971

Toe of slope, near right abutment. Seepage appears to flow from location directly across from end of upstream vertical concrete face.

APPENDIX 4

HYDROLOGIC COMPUTATIONS

LAKE KALMIA DAM

JOB NO.

SQUARES
1/4 IN. SCALE

0 1 2 3 4 5 6 7 8 9 10 11 12 13 14 15 16 17 18 19 20 21 22 23 24 25 26 27 28 29 30

Time of Concentration① Texas Highway Methodall overland, = 5,300 ft. slope = $\frac{715-410}{5,300} = 0.058 = 5.8\%$ From the Texas Highway method chart in Design of Small Dams, $v = 2.0$ fps for woodlands.

$$\text{Time} = \frac{5,300}{2} = 2,650 \text{ sec} = 0.74 \text{ hours}$$

② Soil and Water Conservation Method

$$L = 0.6 T_c = \frac{L^{0.8} (S+1)^{1.67}}{9,000 y^{0.5}}$$

$$\rightarrow T_c = \frac{L^{0.8} (S+1)^{1.67}}{0.6 (9,000) y^{0.5}}$$

$$L = 5,300 \text{ ft.}$$

$$y = 5.8\%$$

$$S = \frac{1,000}{CN} - 10 \quad \text{CN} = 70 \text{ for woods of soil group C, good condition.}$$

$$S = \frac{1,000}{70} - 10 = 4.29$$

$$T_c = \frac{5,300^{0.8} (5.29)^{1.67}}{0.6 (9,000) (5.8)^{0.5}} = 1.18 \text{ hours}$$

③ Weston, or SCS T.R. #55 Methodall overland. slope = 5.8% $\rightarrow v = 0.6$ fps

$$T_c = \frac{5,300}{0.6} = 8,833 \text{ sec} = 2.45 \text{ hours}$$

JOB NO.

SQUARES

1/4 IN. SCALE

0 1 2 3 4 5 6 7 8 9 10 11 12 13 14 15 16 17 18 19 20 21 22 23 24 25 26 27 28 29 30

④ Kerby Method

all overland.

$$T_c = 0.83 \left(\frac{NL}{\sqrt{S}} \right)^{0.467}$$

$$N = 0.7; L = 5,300; S = 0.058$$

$$= 0.83 \left(\frac{0.7(5,300)}{\sqrt{0.058}} \right)^{0.467}$$

$$= 74.94 \text{ min} = 1.25 \text{ hours}$$

$$\text{Average} = \frac{0.74 + 1.18 + 2.45 + 1.25}{4} = 1.4 \text{ hours}$$

$$\text{Lag} = 0.6 T_c = 0.84 \text{ hours}$$

$$\text{Drainage Area} = 0.50 \text{ square miles}$$

39

JOB NO.

SQUARES 0 1 2 3 4 5 6 7 8 9 10 11 12 13 14 15 16 17 18 19 20 21 22 23 24 25 26 27 28 29 30
1/4 IN. SCALEStage Vs. Discharge

The hydraulic profile of Lake Kalmia is shown on P. 4.
See the profile for sections of dam crest, referred to as ①, ②, etc

Spillway (⑧) $Q = C L H^{3/2}$ $C = 3.0$ for Broad Crested concrete weir
 $Q = 3.0 (4.3) (E-410.3)^{3/2}$

Top of Dam (sections ⑥, ⑦, ⑨, ⑩, ⑪, and ⑫) $C = 2.7$ for all sections

Section ⑥ is a sloping weir 50' long, w/ one end at 411.2' and the other at 411.8' (411.5' avg.). The slope is $\frac{50}{0.6} = 83.3 H:1V$.

Section ⑦ is a level 98' weir at 411.2'.


Section ⑨ is a sloping weir 49.7 feet long, with one end at 411.1' and the other at 411.3' (411.2' avg.). The slope is $\frac{49.7}{0.2} = 238.5 H:1V$.

Section ⑩ is a sloping weir 50 feet long, with ends at 411.3' and 411.4' (avg. = 411.35). The slope is $\frac{50}{0.1} = 500 H:1V$.

Section ⑪ is a 50' level weir at 411.4

Section ⑫ is a 50' sloping weir with ends at 411.4 and 412.0 (avg. = 411.7'). The slope is $\frac{50}{0.6} = 83.33 H:1V$

For a sloping weir only partially submerged:




$$Q = C L_{sub} H_{avg}^{3/2}$$

$$H_{avg} = \frac{0 + h}{2} = 0.5 h$$

$$L_{sub} = z h$$

$$Q = C (z)(h) (0.5(h))^{3/2}$$

For a sloping weir fully submerged:




$$Q = C L_{sub} H_{avg}^{3/2}$$

$$= C L (h - z)^{3/2}$$

Natural Saddle Em. s/w

Hill

Dam



Elevation (Ft. above MGLD)

405

400

ANDERSON-NICHOLS

VERNON BOSTON CONCORD

Lake Kalmia Dam
Hydraulic Profile

DATE: 6/25/81 SCALE: 1" = 5' V, 1" = 100' H JOB NO. 3670-08 SHEET NO. P. 4 of 15

JOB NO.

JARES IN. SCALE 0 1 2 3 4 5 6 7 8 9 10 11 12 13 14 15 16 17 18 19 20 21 22 23 24 25 26 27 28 29 30

We will compute Q at 410.3, 410.7, 411.1, 411.5, 412.0, 412.5, 413.0, 413.5

at 410.3, 410.7, and 411.1 - no flow

$$\text{at } 411.5: Q_6 = 2.7 (83.3) (E - 411.2) (0.5 (E - 411.2))^{3/2}$$

$$Q_7 = 2.7 (98.) (E - 411.2)^{3/2}$$

$$Q_9 = 2.7 (47.7) (E - 411.2)^{3/2}$$

$$Q_{10} = 2.7 (50) (E - 411.35)^{3/2}$$

$$Q_{11} = 2.7 (50) (E - 411.4)^{3/2}$$

$$Q_{12} = 2.7 (83.3) (E - 411.4) (0.5 (E - 411.4))^{3/2}$$

$$Q = Q_6 + Q_7 + Q_9 + Q_{10} + Q_{11} + Q_{12}$$

at 412.0, 412.5, 413.0, and 413.5

$$Q_6 = 2.7 (50) (E - 411.5)^{3/2}$$

$$Q_{12} = 2.7 (50) (E - 411.7)^{3/2}$$

$$Q_7, Q_9, Q_{10}, Q_{11} \text{ The same as at } 411.5$$

Natural Saddle (sections ①, ②, ③, ④) $C = 2.6$ for all sections

Section ① is a 2H:1V sloping weir with its low end at 411.5'

Section ② is an even crested 120 foot weir at 411.5'

Section ③ is a 145.5 H to 1V weir 160 feet long, with one end at 411.5 and the other at 412.6'

Section ④ is a 16.2 H:1V sloping weir 120 feet long, with one end at 412.6' and the other at 420.0'.

at 410.3, 410.7, 411.1, 411.5 - no flow

$$\text{at } 412.0 \text{ and } 412.5: Q_1 = 2.6 (2) (E - 411.5) (0.5 (E - 411.5))^{3/2}$$

$$Q_2 = 2.6 (120) (E - 411.5)^{3/2}$$

$$Q_3 = 2.6 (145.5) (E - 411.5) (0.5 (E - 411.5))^{3/2}$$

$$Q_4 = \text{no flow}$$

$$Q = Q_1 + Q_2 + Q_3 + Q_4$$

JOB NO.

SQUARES 0 1 2 3 4 5 6 7 8 9 10 11 12 13 14 15 16 17 18 19 20 21 22 23 24 25 26 27 28 29 30
1/4 IN. SCALE

$$\text{at } 413.0 \text{ and } 413.5 : Q_3 = 2.6(160)(E-412.05)^{3/2}$$

$$Q_4 = 2.6(16.2)(E-412.6)(0.5(E-412.6))^{3/2}$$

Q_1 and Q_2 the same as before

Side slopes: (sections ⑤ and ③), $C = 2.6$

Section ⑤ is a 9.8 H:1V sloping weir, with one end at 411.8',
The other at 420.0' and 415.9' average.

Section ③ is a 20H:1V sloping weir with its low end at 412.0

at 410.3, 410.7, 411.1, and 411.5: no flow


$$\text{at } 412.0, 412.5, 413.0, \text{ and } 413.5 : Q_5 = 2.6(9.8)(E-411.8)(0.5(E-411.8))^{3/2}$$

$$Q_{13} = 2.6(20)(E-412.0)(0.5(E-412.0))^{3/2}$$

Elevation (ft. above NVD)	Q_{spillway} (cfs)	$Q_{\text{Top of Dam}}$ (cfs)	Q_{saddle} (cfs)	$Q_{\text{side slopes}}$ (cfs)	Q_{Total} (cfs)
410.3	0	0	0	0	0
410.7	3.3	0	0	0	3.3
411.1	9.2	0	0	0	9.2
411.5	17.0	81	0	0	98
412.0	29	485	134	0	648
412.5	42	1,137	448	7	1,634
413.0	57	1,957	965	33	3,012
413.5	74	2,917	1,631	85	4,707

Lake Kalma Dam Stage Versus Discharge

Page 7 of 15



JOB NO.


SQUARES
1/4 IN. SCALE

0 1 2 3 4 5 6 7 8 9 10 11 12 13 14 15 16 17 18 19 20 21 22 23 24 25 26 27 28 29 30

Stage versus Storage

At the spillway crest, elevation 410.3, the pond has an area of 19.2 acres. At elevation 420, the surface area would be about 33 acres. Assume a linear increase in surface area with stage. Storage at the spillway crest = 77 ac-ft (avg depth = 4 ft.). Storage = 0 at 404.

Elevation (ft. above NGVD)	ΔH	Surface Area (Acres)	Avg. S. A. (Acres)	Incremental Storage (Ac-Ft)	Cumulative Storage (Ac-Ft)
404.	-	-	-	-	0.0
410.3	-	19.2	-	-	77.0
410.7	0.4	19.8	19.5	7.8	84.8
411.1	0.4	20.3	20.05	8.0	92.8
411.5	0.4	20.9	20.6	8.2	101.0
412.0	0.5	21.6	21.25	10.6	111.6
412.5	0.5	22.3	21.95	11.0	122.6
413.0	0.5	23.0	22.65	11.3	133.9
413.5	0.5	23.8	23.4	11.7	145.6



JOB NO.

SQUARES 0 1 2 3 4 5 6 7 8 9 10 11 12 13 14 15 16 17 18 19 20 21 22 23 24 25 26 27 28 29 3
1/4 IN. SCALERainfall - 100 year flood

The 100-year flood is the test flood for this dam. For a T_c of 1.4 hours, we will use a 2-hour storm. (5 minute time steps). Use the "synthetic storm from depth-duration data", Hydro-35 NWS

Duration100-year rainfall

5 minutes

0.78" 1.

10 "

 $0.59 D_{15} + 0.41 D_5 = 1.31" 3.$

15 "

1.68" 1.

30 "

 $0.49 D_{60} + 0.51 D_{15} = 2.38" 3.$

60 "

3.10" 1.

120 "


3.70" 2.

P.11 shows a mass curve for the peak 100 year depth versus duration for Lake Kalmia on Log-Log paper. The increments of rain are given on page 12. The storm will have the largest in the 13th time interval, 2nd largest in the 12th, 3rd largest in 14th, etc.

1. NWS Hydro-35

2. NWS TP-40

3. Interpolation from NWS Hydro 35.



JOB NO.

SQUARES
1/4 IN. SCALE

0 1 2 3 4 5 6 7 8 9 10 11 12 13 14 15 16 17 18 19 20 21 22 23 24 25 26 27 28 29 30

	<u>Duration (min.)</u>	<u>Depth (in.)</u>	<u>ΔT (min.)</u>	<u>Δ Rain (in.)</u>	<u>Ranking</u>	<u>Time int.</u>
1						
2						
3	0	0	5	0.78	1	13
4	5	0.78	5	0.53	2	12
5	10	1.31	5	0.37	3	14
6	15	1.68	5	0.29	4	11
7	20	1.97	5	0.22	5	15
8	25	2.19	5	0.19	6	10
9	30	2.38	5	0.18	7	16
10	35	2.56	5	0.14	8	9
11	40	2.70	5	0.10	9	17
12	45	2.80	5	0.10	10	8
13	50	2.90	5	0.10	11	18
14	55	3.00	5	0.10	12	7
15	60	3.10	5	0.07	13	19
16	65	3.17	5	0.06	14	6
17	70	3.23	5	0.06	15	20
18	75	3.29	5	0.05	16	5
19	80	3.34	5	0.05	17	21
20	85	3.39	5	0.05	18	4
21	90	3.44	5	0.05	19	22
22	95	3.49	5	0.05	20	3
23	100	3.54	5	0.04	21	23
24	105	3.58	5	0.04	22	2
25	110	3.62	5	0.04	23	24
26	115	3.66	5	0.04	24	1
27	120	3.70				
28						
29						
30						
31						
32						
33						
34						
35						
36						
37						
38						
39						
40						

So input incremental rainfall for 5 minute increments is 0.04, 0.04, 0.05, 0.05,

0.06, 0.06, 0.10, 0.10, 0.14, 0.19, 0.29, 0.53, 0.78, 0.37, 0.22, 0.18, 0.19, 0.10, 0.07,

0.06, 0.05, 0.05, 0.04, 0.04

JOB NO.

SQUARES 0 1 2 3 4 5 6 7 8 9 10 11 12 13 14 15 16 17 18 19 20 21 22 23 24 25 26 27 28 29 30
1/4 IN. SCALEOvertopping Analysis

For this small, low-hazard dam the 100 year storm was used to generate a test flood. The storm gives a peak outflow of 494 cfs, which is 54 times as large as the spillway capacity. The peak 100-year stage would be 41.86 feet, 0.86 feet over the dam crest.

At this stage, the flow is as follows

over spillway	= 26 cfs
over dam	= 372 cfs
over natural saddle	= 96 cfs
overside slopes	= 0.0 cfs

494 cfs

JOB NO.

 SQUARES 0 1 2 3 4 5 6 7 8 9 10 11 12 13 14 15 16 17 18 19 20 21 22 23 24 25 26 27 28 29 30
 1/4 IN. SCALE
Drawdown Time

The 8" pipe shown on the plans as a low-level outlet for Lake Kalmia may not be in operating condition. If it is, its invert is at about 404.0. Assume:

① no inflow

 ② inlet control on pipe. $Q = C A \sqrt{2g} \sqrt{H}$. $C = 0.61$, $A = \pi (\frac{1}{3})^2 = 0.349 \text{ ft}^2$
 $Q = 0.61 (0.349) (\sqrt{2g}) (E - 404.33)^{1/2} = 1.71 (E - 404.33)^{1/2}$

 ③ storage follows $S = C h^N$. $h = E - 402$. given $S = 77$ at $h = 6.3$ and $S = 145.6$ at $h = 9.5$ (page 8):

$$77 = C 6.3^N$$

$$\ln 77 = \ln C + N \ln 6.3$$

$$\rightarrow \ln C = 4.344 - 1.841N$$

$$\text{and } 145.6 = C 9.5^N$$

$$\ln 145.6 = \ln C + N \ln 9.5$$

substitute for $\ln C$

$$\ln 145.6 = 4.344 - 1.841N + N \ln 9.5$$

$$4.981 - 4.344 = -1.841N + 2.251N$$

$$N = 1.554$$

$$\rightarrow \ln C = 4.344 - 2.116N = 1.483 \rightarrow C = 4407$$

$$\text{so } S = 4407 (E - 404)^{1.554}$$

④ $Ac - \text{ft/day} = Q_{\text{avg}} \times 1.9835$

⑤ $\text{Days} = \frac{\Delta S}{Ac - \text{ft/day}}$

JOB NO.

SQUARES 0 1 2 3 4 5 6 7 8 9 10 11 12 13 14 15 16 17 18 19 20 21 22 23 24 25 26 27 28 29 30
1/4 IN. SCALE

Elevation (ft. above MVD)	Storage (acre-ft)	ΔS (acre-ft)	Q (cfs)	Qave (cfs)	Ac-ft/day	DAYS
410.3	77	-	4.2			
		23.2		3.4	7.74	3.0
409	53.8		3.7			
		15.8		3.5	6.44	2.3
408	38.0		3.3			
		13.7		3.1	6.15	2.2
407	24.3		2.8			
		11.4		2.5	4.96	2.3
406	12.4		2.2			
		8.5		1.8	3.57	2.4
405	4.4		1.4			
		4.4		0.7	1.39	3.2
404	0		0			

15.4 days

APPENDIX 5

HEC1 OUTPUT

LAKE KALMIA DAM

```

10.....1.....2.....3.....4.....5.....6.....7.....8.....9.....10
11 LAKE KALMIA DAM INVERTING ANALYSIS TIM BENCH ANCO
12 VFA JERSEY DAM NO. 100 - WARREN COUNTY - BLAIRSTOWN TOWNSHIP
13 100-YEAR STORM (2-HOUR STORM)
14 5 0 200
15 2 1
16
17
18
19
20
21
22
23
24
25
26
27
28
29
30
31
32
33
34
35
36
37
38
39
40
41
42
43
44
45
46
47
48
49
50
51
52
53
54
55
56
57
58
59
60
61
62
63
64
65
66
67
68
69
70
71
72
73
74
75
76
77
78
79
80
81
82
83
84
85
86
87
88
89
90
91
92
93
94
95
96
97
98
99
100
101
102
103
104
105
106
107
108
109
110
111
112
113
114
115
116
117
118
119
120
121
122
123
124
125
126
127
128
129
130
131
132
133
134
135
136
137
138
139
140
141
142
143
144
145
146
147
148
149
150
151
152
153
154
155
156
157
158
159
160
161
162
163
164
165
166
167
168
169
170
171
172
173
174
175
176
177
178
179
180
181
182
183
184
185
186
187
188
189
190
191
192
193
194
195
196
197
198
199
200
201
202
203
204
205
206
207
208
209
210
211
212
213
214
215
216
217
218
219
220
221
222
223
224
225
226
227
228
229
230
231
232
233
234
235
236
237
238
239
240
241
242
243
244
245
246
247
248
249
250
251
252
253
254
255
256
257
258
259
260
261
262
263
264
265
266
267
268
269
270
271
272
273
274
275
276
277
278
279
280
281
282
283
284
285
286
287
288
289
290
291
292
293
294
295
296
297
298
299
300
301
302
303
304
305
306
307
308
309
310
311
312
313
314
315
316
317
318
319
320
321
322
323
324
325
326
327
328
329
330
331
332
333
334
335
336
337
338
339
340
341
342
343
344
345
346
347
348
349
350
351
352
353
354
355
356
357
358
359
360
361
362
363
364
365
366
367
368
369
370
371
372
373
374
375
376
377
378
379
380
381
382
383
384
385
386
387
388
389
390
391
392
393
394
395
396
397
398
399
400
401
402
403
404
405
406
407
408
409
410
411
412
413
414
415
416
417
418
419
420
421
422
423
424
425
426
427
428
429
430
431
432
433
434
435
436
437
438
439
440
441
442
443
444
445
446
447
448
449
450
451
452
453
454
455
456
457
458
459
460
461
462
463
464
465
466
467
468
469
470
471
472
473
474
475
476
477
478
479
480
481
482
483
484
485
486
487
488
489
490
491
492
493
494
495
496
497
498
499
500
501
502
503
504
505
506
507
508
509
510
511
512
513
514
515
516
517
518
519
520
521
522
523
524
525
526
527
528
529
530
531
532
533
534
535
536
537
538
539
540
541
542
543
544
545
546
547
548
549
550
551
552
553
554
555
556
557
558
559
560
561
562
563
564
565
566
567
568
569
570
571
572
573
574
575
576
577
578
579
580
581
582
583
584
585
586
587
588
589
590
591
592
593
594
595
596
597
598
599
600
601
602
603
604
605
606
607
608
609
610
611
612
613
614
615
616
617
618
619
620
621
622
623
624
625
626
627
628
629
630
631
632
633
634
635
636
637
638
639
640
641
642
643
644
645
646
647
648
649
650
651
652
653
654
655
656
657
658
659
660
661
662
663
664
665
666
667
668
669
670
671
672
673
674
675
676
677
678
679
680
681
682
683
684
685
686
687
688
689
690
691
692
693
694
695
696
697
698
699
700
701
702
703
704
705
706
707
708
709
710
711
712
713
714
715
716
717
718
719
720
721
722
723
724
725
726
727
728
729
730
731
732
733
734
735
736
737
738
739
740
741
742
743
744
745
746
747
748
749
750
751
752
753
754
755
756
757
758
759
760
761
762
763
764
765
766
767
768
769
770
771
772
773
774
775
776
777
778
779
780
781
782
783
784
785
786
787
788
789
790
791
792
793
794
795
796
797
798
799
800
801
802
803
804
805
806
807
808
809
810
811
812
813
814
815
816
817
818
819
820
821
822
823
824
825
826
827
828
829
830
831
832
833
834
835
836
837
838
839
840
841
842
843
844
845
846
847
848
849
850
851
852
853
854
855
856
857
858
859
860
861
862
863
864
865
866
867
868
869
870
871
872
873
874
875
876
877
878
879
880
881
882
883
884
885
886
887
888
889
890
891
892
893
894
895
896
897
898
899
900
901
902
903
904
905
906
907
908
909
910
911
912
913
914
915
916
917
918
919
920
921
922
923
924
925
926
927
928
929
930
931
932
933
934
935
936
937
938
939
940
941
942
943
944
945
946
947
948
949
950
951
952
953
954
955
956
957
958
959
960
961
962
963
964
965
966
967
968
969
970
971
972
973
974
975
976
977
978
979
980
981
982
983
984
985
986
987
988
989
990
991
992
993
994
995
996
997
998
999
1000
1001
1002
1003
1004
1005
1006
1007
1008
1009
1010
1011
1012
1013
1014
1015
1016
1017
1018
1019
1020
1021
1022
1023
1024
1025
1026
1027
1028
1029
1030
1031
1032
1033
1034
1035
1036
1037
1038
1039
1040
1041
1042
1043
1044
1045
1046
1047
1048
1049
1050
1051
1052
1053
1054
1055
1056
1057
1058
1059
1060
1061
1062
1063
1064
1065
1066
1067
1068
1069
1070
1071
1072
1073
1074
1075
1076
1077
1078
1079
1080
1081
1082
1083
1084
1085
1086
1087
1088
1089
1090
1091
1092
1093
1094
1095
1096
1097
1098
1099
1100
1101
1102
1103
1104
1105
1106
1107
1108
1109
1110
1111
1112
1113
1114
1115
1116
1117
1118
1119
1120
1121
1122
1123
1124
1125
1126
1127
1128
1129
1130
1131
1132
1133
1134
1135
1136
1137
1138
1139
1140
1141
1142
1143
1144
1145
1146
1147
1148
1149
1150
1151
1152
1153
1154
1155
1156
1157
1158
1159
1160
1161
1162
1163
1164
1165
1166
1167
1168
1169
1170
1171
1172
1173
1174
1175
1176
1177
1178
1179
1180
1181
1182
1183
1184
1185
1186
1187
1188
1189
1190
1191
1192
1193
1194
1195
1196
1197
1198
1199
1200
1201
1202
1203
1204
1205
1206
1207
1208
1209
1210
1211
1212
1213
1214
1215
1216
1217
1218
1219
1220
1221
1222
1223
1224
1225
1226
1227
1228
1229
1230
1231
1232
1233
1234
1235
1236
1237
1238
1239
1240
1241
1242
1243
1244
1245
1246
1247
1248
1249
1250
1251
1252
1253
1254
1255
1256
1257
1258
1259
1260
1261
1262
1263
1264
1265
1266
1267
1268
1269
1270
1271
1272
1273
1274
1275
1276
1277
1278
1279
1280
1281
1282
1283
1284
1285
1286
1287
1288
1289
1290
1291
1292
1293
1294
1295
1296
1297
1298
1299
1300
1301
1302
1303
1304
1305
1306
1307
1308
1309
1310
1311
1312
1313
1314
1315
1316
1317
1318
1319
1320
1321
1322
1323
1324
1325
1326
1327
1328
1329
1330
1331
1332
1333
1334
1335
1336
1337
1338
1339
1340
1341
1342
1343
1344
1345
1346
1347
1348
1349
1350
1351
1352
1353
1354
1355
1356
1357
1358
1359
1360
1361
1362
1363
1364
1365
1366
1367
1368
1369
1370
1371
1372
1373
1374
1375
1376
1377
1378
1379
1380
1381
1382
1383
1384
1385
1386
1387
1388
1389
1390
1391
1392
1393
1394
1395
1396
1397
1398
1399
1400
1401
1402
1403
1404
1405
1406
1407
1408
1409
1410
1411
1412
1413
1414
1415
1416
1417
1418
1419
1420
1421
1422
1423
1424
1425
1426
1427
1428
1429
1430
1431
1432
1433
1434
1435
1436
1437
1438
1439
1440
1441
1442
1443
1444
1445
1446
1447
1448
1449
1450
1451
1452
1453
1454
1455
1456
1457
1458
1459
1460
1461
1462
1463
1464
1465
1466
1467
1468
1469
1470
1471
1472
1473
1474
1475
1476
1477
1478
1479
1480
1481
1482
1483
1484
1485
1486
1487
1488
1489
1490
1491
1492
1493
1494
1495
1496
1497
1498
1499
1500
1501
1502
1503
1504
1505
1506
1507
1508
1509
1510
1511
1512
1513
1514
1515
1516
1517
1518
1519
1520
1521
1522
1523
1524
1525
1526
1527
1528
1529
1530
1531
1532
1533
1534
1535
1536
1537
1538
1539
1540
1541
1542
1543
1544
1545
1546
1547
1548
1549
1550
1551
1552
1553
1554
1555
1556
1557
1558
1559
1560
1561
1562
1563
1564
1565
1566
1567
1568
1569
1570
1571
1572
1573
1574
1575
1576
1577
1578
1579
1580
1581
1582
1583
1584
1585
1586
1587
1588
1589
1590
1591
1592
1593
1594
1595
1596
1597
1598
1599
1600
1601
1602
1603
1604
1605
1606
1607
1608
1609
1610
1611
1612
1613
1614
1615
1616
1617
1618
1619
1620
1621
1622
1623
1624
1625
1626
1627
1628
1629
1630
1631
1632
1633
1634
1635
1636
1637
1638
1639
1640
1641
1642
1643
1644
1645
1646
1647
1648
1649
1650
1651
1652
1653
1654
1655
1656
1657
1658
1659
1660
1661
1662
1663
1664
1665
1666
1667
1668
1669
1670
1671
1672
1673
1674
1675
1676
1677
1678
1679
1680
1681
1682
1683
1684
1685
1686
1687
1688
1689
1690
1691
1692
1693
1694
1695
1696
1697
1698
1699
1700
1701
1702
1703
1704
1705
1706
1707
1708
1709
1710
1711
1712
1713
1714
1715
1716
1717
1718
1719
1720
1721
1722
1723
1724
1725
1726
1727
1728
1729
1730
1731
1732
1733
1734
1735
1736
1737
1738
1739
1740
1741
1742
1743
1744
1745
1746
1747
1748
1749
1750
1751
1752
1753
1754
1755
1756
1757
1758
1759
1760
1761
1762
1763
1764
1765
1766
1767
1768
1769
1770
1771
1772
1773
1774
1775
1776
1777
1778
1779
1780
1781
1782
1783
1784
1785
1786
1787
1788
1789
1790
1791
1792
1793
1794
1795
1796
1797
1798
1799
1800
1801
1802
1803
1804
1805
1806
1807
1808
1809
1810
1811
1812
1813
1814
1815
1816
1817
1818
1819
1820
1821
1822
1823
1824
1825
1826
1827
1828
1829
1830
1831
1832
1833
1834
1835
1836
1837
1838
1839
1840
1841
1842
1843
1844
1845
1846
1847
1848
1849
1850
1851
1852
1853
1854
1855
1856
1857
1858
1859
1860
1861
1862
1863
1864
1865
1866
1867
1868
1869
1870
1871
1872
1873
1874
1875
1876
1877
1878
1879
1880
1881
1882
1883
1884
1885
1886
1887
1888
1889
1890
1891
1892
1893
1894
1895
1896
1897
1898
1899
1900
1901
1902
1903
1904
1905
1906
1907
1908
1909
1910
1911
1912
1913
1914
1915
1916
1917
1918
1919
1920
1921
1922
1923
1924
1925
1926
1927
1928
1929
1930
1931
1932
1933
1934
1935
1936
1937
1938
1939
1940
1941
1942
1943
1944
1945
1946
1947
1948
1949
1950
1951
1952
1953
1954
1955
1956
1957
1958
1959
1960
1961
1962
1963
1964
1965
1966
1967
1968
1969
1970
1971
1972
1973
1974
1975
1976
1977
1978
1979
1980
1981
1982
1983
1984
1985
1986
1987
1988
1989
1990
1991
1992
1993
1994
1995
1996
1997
1998
1999
2000
2001
2002
2003
2004
2005
2006
2007
2008
2009
2010
2011
2012
2013
2014
2015
2016
2017
2018
2019
2020
2021
2022
2023
2024
2025
2026
2027
2028
2029
2030
2031
2032
2033
2034
2035
2036
2037
2038
2039
2040
2041
2042
2043
2044
2045
2046
2047
2048
2049
2050
2051
2052
2053
2054
2055
2056
2057
2058
2059
2060
2061
2062
2063
2064
2065
2066
2067
2068
2069
2070
2071
2072
2073
2074
2075
2076
2077
2078
2079
2080
2081
2082
2083
2084
2085
2086
2087
2088
2089
2090
2091
2092
2093
2094
2095
2096
2097
2098
2099
2100
2101
2102
2103
2104
2105
2106
2107
2108
2109
2110
2111
2112
2113
2114
2115
2116
2117
2118
2119
2120
2121
2122
2123
2124
2125
2126
2127
2128
2129
2130
2131
2132
2133
2134
2135
2136
2137
2138
2139
2140
2141
2142
2143
2144
2145
2146
2147
2148
2149
2150
2151
2152
2153
2154
2155
2156
2157
2158
2159
2160
2161
2162
2163
2164
2165
2166
2167
2168
2169
2170
2171
2172
2173
2174
2175
2176
2177
2178
2179
2180
2181
2182
2183
2184
2185
2186
2187
2188
2189
2190
2191
2192
2193
2194
2195
2196
2197
2198
2199
2200
2201
2202
2203
2204
2205
2206
2207
2208
2209
2210
2211
2212
2213
2214
2215
2216
2217
2218
2219
2220
2221
2222
2223
2224
2225
2226
2227
2228
2229
2230
2231
2232
2233
2234
2235
2236
2237
2238
2239
2240
2241
2242
2243
2244
2245
2246
2247
2248
2249
2250
2251
2252
2253
2254
2255
2256
2257
2258
2259
2260
2261
2262
2263
2264
2265
2266
2267
2268
2269
2270
2271
2272
2273
2274
2275
2276
2277
2278
2279
2280
2281
2282
2283
2284
2285
2286
2287
2288
2289
2290
2291
2292
2293
2294
2295
2296
2297
2298
2299
2300
2301
2302
2303
2304
2305
2306
2307
2308
2309
2310
2311
2312
2313
2314
2315
2316
2317
2318
2319
2320
2321
2322
2323
2324
2325
2326
2327
2328
2329
2330
2331
2332
2333
2334
2335
2336
2337
2338
2339
2340
2341
2342
2343
2344
2345
2346
2347
2348
2349
2350
2351
2352
2353
2354
2355
2356
2357
2358
2359
2360
2361
2362
2363
2364
2365
2366
2367
2368
2369
2370
2371
2372
2373
2374
2375
2376
2377
2378
2379
2380
2381
2382
2383
2384
2385
2386
2387
2388
2389
2390
2391
2392
2393
2394
2395
2396
2397
2398
2399
2400
2401
2402
2403
2404
2405
2406
2407
2408
2409
2410
2411
2412
2413
2414
2415
2416
2417
2418
2419
2420
2421
2422
2423
2424
2425
2426
2427
2428
2429
2430
2431
2432
2433
2434
2435
2436
2437
2438
2439
2440
2441
2442
2443
2444
2445
2446
2447
2448
2449
2450
2451
2452
2453
2454
2455
2456
2457
2458
2459
2460
2461
2462
2463
2464
2465
2466
2467
2468
2469
2470
2471
2472
2473
2474
2475
2476
2477
2478
2479
2480
2481
2482
2483
2484
2485
2486
2487
2488
2489
2490
2491
2492
2493
2494
2495
2496
2497
2498
2499
2500
2501
2502
2503
2504
2505
2506
2507
2508
2509
2510
2511
2512
2513
2514
2515
2516
2517
2518
2519
2520
2521
2522
2523
2524
2525
2526
2527
2528
2529
2530
2531
2532
2533
2534
2535
2536
2537
2538
2539
2540
2541
2542
2543
2544
2545
2546
2547
2548
2549
2550
2551
2552
2553
2554
2555
2556
2557
2558
2559
2560
2561
2562
2563
2564
2565
2566
2567
2568
2569
2570
2571
2572
2573
2574
2575
2576
2577
2578
2579
2580
2581
2582
2583
2584
2585
2586
2587
2588
2589
2590
2591
2592
2593
2594
2595
2596
2597
2598
2599
2600
2601
2602
2603
2604
2605
2606
2607
2608
2609
2610
2611
2612
2613
2614
2615
2616
2617
2618
2619
2620
2621
2622
2623
2624
2625
2626
2627
2628
2629
2630
2631
2632
2633
2634
2635
2636
2637
2638
2639
2640
2641
2642
2643
2644
2645
2646
2647
2648
2649
2650
2651
2652
2653
2654
2655
2656
2657
2658
2659
2660
2661
26
```

 FLOOD HYDROGRAPH PACKAGE (HEC-1)
 FEBRUARY 1971
 KUH LATE08/11/61 TIME 16.33.13

LAKE KALMIA DAM OVERTOPPING ANALYSIS TOM COUCH ANCO
 NEW JERSEY DAM NO. 166 - WARREN COUNTY - BLAIRSTOWN TOWNSHIP
 100-YEAR STORM (2-HOUR STORM)

5 IO OUTPUT CONTROL VARIABLES PRINT CONTROL
 IPLOT 1 PLOT CONTROL
 USCAL 0 HYDROGRAPH PLOT SCALE
 YES PRINT DIAGNOSTIC MESSAGES

17 HYDROGRAPH TIME DATA 5 MINUTES IN COMPUTATION INTERVAL
 DATE 1 0000 STARTING DATE
 TIME 200 NUMBER OF HYDROGRAPH ORDINATES
 NO DATE 1 1635 ENDING DATE
 NO TIME ENDING TIME

COMPUTATION INTERVAL 0.06 HOURS
 TOTAL TIME BASE 16.56 HOURS

ENGLISH UNITS
 DRAINAGE AREA SQUARE MILES
 PRECIPITATION DEPTH INCHES
 LENGTH OF ELEVATION FEET
 FLOW CUBIC FEET PER SECOND
 STORAGE VOLUME ACRES
 SURFACE AREA ACRES
 TEMPERATURE DEGREES FAHRENHEIT

*** ** ** ** **

6 KK

 AI

LAKE KALMIA INFLOW HYDROGRAPH
 INFLW FRM SCS UNIT GRAPH COMPUTATIONS

10 IN TIME DATA FOR INPUT TIME SERIES
 JDATE 1 0000 STARTING DATE
 JTIME 1 0000 STARTING TIME

SUBBASIN RUNOFF DATA

6 EA SUBBASIN CHARACTERISTICS
 TAREA 0.50 SUBBASIN AREA

9 EF BASF FLOW CHARACTERISTICS
 CTRG 1.00 INITIAL FLOW
 PCCSR 1.00 BEGINNING FLOW RECESSON
 RTLGR 1.0000 RECESSON CONSTANT

PRECIPITATION DATA

17 FT TOTAL STORM STATIONS INFLOW
 16 PW WEIGTHS 1.00

15 PR RECORDING STATIONS INFLOW
 16 PW WEIGTHS 1.00

 U.S. ARMY CORPS OF ENGINEERS
 THE HYDROLOGIC ENGINEERING CENTER
 309 SECOND STREET
 DAVIS, CALIFORNIA 95616
 (916) 440-3285 DR (FTS) 448-3285

19 LU UNIFORM LOSS RATE 1.00 INITIAL LOSS RATE
 STATION 0.10 UNIFORM LOSS RATE
 CASE 0.0 PERCENT IMPERVIOUS AREA
 20 UD SCS DIMENSIONLESS UNITGRAPH
 FLAG 0.04 LAG

PRECIPITATION STATION DATA

STATION TOTAL AVG. ANNUAL WEIGHT
 INFLUW 3.73 0.0 1.00

TEMPORAL DISTRIBUTIONS

STATION INFLUW WEIGHT = 1.00
 0.04 0.05 0.05 0.06 0.10 0.14 0.19
 0.23 0.76 0.37 0.18 0.10 0.10 0.06
 0.03 0.04 0.04

UNIT HYDROGRAPH ORDINATES

52 END-OF-PERIOD ORDINATES
 273. 78. 263. 273.
 79. 231. 108. 92.
 17. 59. 12. 20.
 4. 13. 5. 1.
 0. 3. 2. 1.

HYDROGRAPH AT STATION A1

EQ	WDR	HRMN	TMO	RAIN	LOSS	EXCESS	COMP	DA	MON	HRMN	JRD	RAIN	LOSS	EXCESS	COMP
1	0000	0.00	1	0.00	0.00	0.00	2.	1	0000	0000	101	0.00	0.00	0.00	2.
1	0005	0.00	2	0.00	0.00	0.00	2.	1	0005	0005	102	0.00	0.00	0.00	2.
1	0010	0.00	3	0.00	0.00	0.00	2.	1	0010	0010	103	0.00	0.00	0.00	2.
1	0015	0.00	4	0.00	0.00	0.00	2.	1	0015	0015	104	0.00	0.00	0.00	2.
1	0020	0.00	5	0.00	0.00	0.00	2.	1	0020	0020	105	0.00	0.00	0.00	2.
1	0025	0.00	6	0.00	0.00	0.00	2.	1	0025	0025	106	0.00	0.00	0.00	2.
1	0030	0.00	7	0.00	0.00	0.00	2.	1	0030	0030	107	0.00	0.00	0.00	2.
1	0035	0.00	8	0.00	0.00	0.00	2.	1	0035	0035	108	0.00	0.00	0.00	2.
1	0040	0.00	9	0.00	0.00	0.00	2.	1	0040	0040	109	0.00	0.00	0.00	2.
1	0045	0.00	10	0.00	0.00	0.00	2.	1	0045	0045	110	0.00	0.00	0.00	2.
1	0050	0.00	11	0.00	0.00	0.00	2.	1	0050	0050	111	0.00	0.00	0.00	2.
1	0055	0.00	12	0.00	0.00	0.00	2.	1	0055	0055	112	0.00	0.00	0.00	2.
1	0100	0.00	13	0.00	0.00	0.00	2.	1	0100	0100	113	0.00	0.00	0.00	2.
1	0105	0.00	14	0.00	0.00	0.00	2.	1	0105	0105	114	0.00	0.00	0.00	2.
1	0110	0.00	15	0.00	0.00	0.00	2.	1	0110	0110	115	0.00	0.00	0.00	2.
1	0115	0.00	16	0.00	0.00	0.00	2.	1	0115	0115	116	0.00	0.00	0.00	2.
1	0120	0.00	17	0.00	0.00	0.00	2.	1	0120	0120	117	0.00	0.00	0.00	2.
1	0125	0.00	18	0.00	0.00	0.00	2.	1	0125	0125	118	0.00	0.00	0.00	2.
1	0130	0.00	19	0.00	0.00	0.00	2.	1	0130	0130	119	0.00	0.00	0.00	2.
1	0135	0.00	20	0.00	0.00	0.00	2.	1	0135	0135	120	0.00	0.00	0.00	2.
1	0140	0.00	21	0.00	0.00	0.00	2.	1	0140	0140	121	0.00	0.00	0.00	2.
1	0145	0.00	22	0.00	0.00	0.00	2.	1	0145	0145	122	0.00	0.00	0.00	2.
1	0150	0.00	23	0.00	0.00	0.00	2.	1	0150	0150	123	0.00	0.00	0.00	2.
1	0155	0.00	24	0.00	0.00	0.00	2.	1	0155	0155	124	0.00	0.00	0.00	2.
1	0200	0.00	25	0.00	0.00	0.00	2.	1	0200	0200	125	0.00	0.00	0.00	2.
1	0205	0.00	26	0.00	0.00	0.00	2.	1	0205	0205	126	0.00	0.00	0.00	2.
1	0210	0.00	27	0.00	0.00	0.00	2.	1	0210	0210	127	0.00	0.00	0.00	2.
1	0215	0.00	28	0.00	0.00	0.00	2.	1	0215	0215	128	0.00	0.00	0.00	2.
1	0220	0.00	29	0.00	0.00	0.00	2.	1	0220	0220	129	0.00	0.00	0.00	2.
1	0225	0.00	30	0.00	0.00	0.00	2.	1	0225	0225	130	0.00	0.00	0.00	2.

.....

.....
.....

.....
.....

.....
.....

.....
.....

.....
.....

.....

.....

.....
.....

.....
.....

.....
.....

.....
.....

.....
.....

.....
.....

.....

21 KK
 TIME (HR) 2.00
 (CFS) 6-HR
 (MGHS) 142
 (AC-FT) 2.645
 MAXIMUM AVERAGE FLOW 16.58-HR
 24-HR 52
 72-HR 52
 2.696
 2.656
 72
 CUMULATIVE AREA = 0.50 SQ MI

*** ** ** ** ** **

 ** ** ** **

ROUTE INFLOW HYDROGRAPH THROUGH LAKE KALMJA

HYDROGRAPH ROUTING DATA

22 KS	STORAGE ROUTING	1	NUMBER OF SUBREACHES
23 SV	STORAGE	0.0	77.0
24 SE	ELEVATION	402.00	410.30
25 SD	DISCHARGE	0.	0.
26 SE	ELEVATION	402.00	410.30
27 SS	SPILLWAY	410.30	SPILLWAY CREST ELEVATION
28 ST	TOP OF DAM	411.10	ELEVATION AT TOP OF DAM

STORAGE	0.0	77.00	84.80	92.80	101.00	111.60	122.60	133.90	145.60
OUTFLOW	0.0	0.0	1.30	9.20	98.00	648.00	1634.00	3012.00	4707.00

A2

STAGE	STORAGE	OUTFLOW	ORD	HR4M	MDN	DA	STAGE	STORAGE	OUTFLOW	ORD	HR4M	MDN	DA
1	90.4	7.	68	000	1	1	10	77.0	0.	1	000	1	1
2	90.3	7.	69	000	1	1	10	77.0	0.	1	000	1	1
3	90.3	7.	70	000	1	1	10	77.0	0.	1	000	1	1
4	90.2	7.	71	000	1	1	10	77.0	0.	1	000	1	1
5	90.2	7.	72	000	1	1	10	77.0	0.	1	000	1	1
6	90.1	7.	73	000	1	1	10	77.0	0.	1	000	1	1
7	90.0	7.	74	000	1	1	10	77.0	0.	1	000	1	1
8	90.0	7.	75	000	1	1	10	77.0	0.	1	000	1	1
9	90.0	7.	76	000	1	1	10	77.0	0.	1	000	1	1
10	90.0	7.	77	000	1	1	10	77.0	0.	1	000	1	1
11	90.0	7.	78	000	1	1	10	77.0	0.	1	000	1	1
12	90.0	7.	79	000	1	1	10	77.0	0.	1	000	1	1
13	90.0	7.	80	000	1	1	10	77.0	0.	1	000	1	1
14	90.0	7.	81	000	1	1	10	77.0	0.	1	000	1	1
15	90.0	7.	82	000	1	1	10	77.0	0.	1	000	1	1
16	90.0	7.	83	000	1	1	10	77.0	0.	1	000	1	1
17	90.0	7.	84	000	1	1	10	77.0	0.	1	000	1	1
18	90.0	7.	85	000	1	1	10	77.0	0.	1	000	1	1
19	90.0	7.	86	000	1	1	10	77.0	0.	1	000	1	1
20	90.0	7.	87	000	1	1	10	77.0	0.	1	000	1	1
21	90.0	7.	88	000	1	1	10	77.0	0.	1	000	1	1
22	90.0	7.	89	000	1	1	10	77.0	0.	1	000	1	1
23	90.0	7.	90	000	1	1	10	77.0	0.	1	000	1	1
24	90.0	7.	91	000	1	1	10	77.0	0.	1	000	1	1
25	90.0	7.	92	000	1	1	10	77.0	0.	1	000	1	1
26	90.0	7.	93	000	1	1	10	77.0	0.	1	000	1	1
27	90.0	7.	94	000	1	1	10	77.0	0.	1	000	1	1
28	90.0	7.	95	000	1	1	10	77.0	0.	1	000	1	1
29	90.0	7.	96	000	1	1	10	77.0	0.	1	000	1	1
30	90.0	7.	97	000	1	1	10	77.0	0.	1	000	1	1
31	90.0	7.	98	000	1	1	10	77.0	0.	1	000	1	1
32	90.0	7.	99	000	1	1	10	77.0	0.	1	000	1	1
33	90.0	7.	100	000	1	1	10	77.0	0.	1	000	1	1
34	90.0	7.	101	000	1	1	10	77.0	0.	1	000	1	1
35	90.0	7.	102	000	1	1	10	77.0	0.	1	000	1	1
36	90.0	7.	103	000	1	1	10	77.0	0.	1	000	1	1
37	90.0	7.	104	000	1	1	10	77.0	0.	1	000	1	1
38	90.0	7.	105	000	1	1	10	77.0	0.	1	000	1	1
39	90.0	7.	106	000	1	1	10	77.0	0.	1	000	1	1
40	90.0	7.	107	000	1	1	10	77.0	0.	1	000	1	1
41	90.0	7.	108	000	1	1	10	77.0	0.	1	000	1	1
42	90.0	7.	109	000	1	1	10	77.0	0.	1	000	1	1
43	90.0	7.	110	000	1	1	10	77.0	0.	1	000	1	1
44	90.0	7.	111	000	1	1	10	77.0	0.	1	000	1	1
45	90.0	7.	112	000	1	1	10	77.0	0.	1	000	1	1
46	90.0	7.	113	000	1	1	10	77.0	0.	1	000	1	1
47	90.0	7.	114	000	1	1	10	77.0	0.	1	000	1	1
48	90.0	7.	115	000	1	1	10	77.0	0.	1	000	1	1
49	90.0	7.	116	000	1	1	10	77.0	0.	1	000	1	1
50	90.0	7.	117	000	1	1	10	77.0	0.	1	000	1	1
51	90.0	7.	118	000	1	1	10	77.0	0.	1	000	1	1
52	90.0	7.	119	000	1	1	10	77.0	0.	1	000	1	1
53	90.0	7.	120	000	1	1	10	77.0	0.	1	000	1	1
54	90.0	7.	121	000	1	1	10	77.0	0.	1	000	1	1
55	90.0	7.	122	000	1	1	10	77.0	0.	1	000	1	1
56	90.0	7.	123	000	1	1	10	77.0	0.	1	000	1	1
57	90.0	7.	124	000	1	1	10	77.0	0.	1	000	1	1
58	90.0	7.	125	000	1	1	10	77.0	0.	1	000	1	1
59	90.0	7.	126	000	1	1	10	77.0	0.	1	000	1	1
60	90.0	7.	127	000	1	1	10	77.0	0.	1	000	1	1
61	90.0	7.	128	000	1	1	10	77.0	0.	1	000	1	1
62	90.0	7.	129	000	1	1	10	77.0	0.	1	000	1	1
63	90.0	7.	130	000	1	1	10	77.0	0.	1	000	1	1
64	90.0	7.	131	000	1	1	10	77.0	0.	1	000	1	1
65	90.0	7.	132	000	1	1	10	77.0	0.	1	000	1	1
66	90.0	7.	133	000	1	1	10	77.0	0.	1	000	1	1
67	90.0	7.	134	000	1	1	10	77.0	0.	1	000	1	1
68	90.0	7.	135	000	1	1	10	77.0	0.	1	000	1	1
69	90.0	7.	136	000	1	1	10	77.0	0.	1	000	1	1
70	90.0	7.	137	000	1	1	10	77.0	0.	1	000	1	1
71	90.0	7.	138	000	1	1	10	77.0	0.	1	000	1	1
72	90.0	7.	139	000	1	1	10	77.0	0.	1	000	1	1
73	90.0	7.	140	000	1	1	10	77.0	0.	1	000	1	1
74	90.0	7.	141	000	1	1	10	77.0	0.	1	000	1	1
75	90.0	7.	142	000	1	1	10	77.0	0.	1	000	1	1
76	90.0	7.	143	000	1	1	10	77.0	0.	1	000	1	1
77	90.0	7.	144	000	1	1	10	77.0	0.	1	000	1	1
78	90.0	7.	145	000	1	1	10	77.0	0.	1	000	1	1
79	90.0	7.	146	000	1	1	10	77.0	0.	1	000	1	1
80	90.0	7.	147	000	1	1	10	77.0	0.	1	000	1	1
81	90.0	7.	148	000	1	1	10	77.0	0.	1	000	1	1
82	90.0	7.	149	000	1	1	10	77.0	0.	1	000	1	1
83	90.0	7.	150	000	1	1	10	77.0	0.	1	000	1	1
84	90.0	7.	151	000	1	1	10	77.0	0.	1	000	1	1
85	90.0	7.	152	000	1	1	10	77.0	0.	1	000	1	1
86	90.0	7.	153	000	1	1	10	77.0	0.	1	000	1	1
87	90.0	7.	154	000	1	1	10	77.0	0.	1	000	1	1
88	90.0	7.	155	000	1	1	10	77.0	0.	1	000	1	1
89	90.0	7.	156	000	1	1	10	77.0	0.	1	000	1	1
90	90.0	7.	157	000	1	1	10	77.0	0.	1	000	1	1
91	90.0	7.	158	000	1	1	10	77.0	0.	1	000	1	1
92	90.0	7.	159	000	1	1	10	77.0	0.	1	000	1	1
93	90.0	7.	160	000	1	1	10	77.0	0.	1	000	1	1
94	90.0	7.	161	000	1	1	10	77.0	0.	1	000	1	1
95	90.0	7.	162	000	1	1	10	77.0	0.	1	000	1	1
96	90.0	7.	163	000	1	1	10	77.0	0.	1	000	1	1
97	90.0	7.	164	000	1	1	10	77.0	0.	1	000	1	1
98	90.0	7.	165	000	1	1	10	77.0	0.	1	000	1	1
99	90.0	7.	166	000	1	1	10	77.0	0.	1	000	1	1
100	90.0	7.	167	000	1	1	10	77.0	0.	1	000	1	1
101	90.0	7.	168	000	1	1	10	77.0	0.	1	000	1	1
102	90.0	7.	169	000	1	1	10	77.0	0.	1	000	1	1
103	90.0	7.	170	000	1	1	10	77.0	0.	1	000	1	1
104	90.0	7.	171	000	1	1	10	77.0	0.	1	000	1	1
105	90.0	7.	172	000	1	1	10	77.0	0.	1	000	1	1
106	90.0	7.	173	000	1	1	10	77.0	0.	1	000	1	1
107	90.0	7.	174	000	1	1	10	77.0	0.	1	000	1	1
108	90.0	7.	175	000	1	1	10	77.0	0.	1	000	1	1
109	90.0	7.	176	000	1	1	10	77.0	0.	1	000	1	1
110	90.0	7.	177	000	1	1	10	77.0	0.	1	000	1	1
111	90.0	7.	178	000	1	1	10	77.0	0.	1	000	1	1
112	90.0	7.	179	000	1	1	10	77.0	0.	1	000	1	1
113	90.0	7.	180	000	1	1	10	77.0	0.	1	000	1	1
114	90.0	7.	181	000	1	1	10	77.0	0.	1	000	1	1
115	90.0	7.	182	000	1	1	10	77.0	0.	1	000	1	1
116	90.0	7.	183	000	1	1	10	77.0	0.	1	000	1	1
117	90.0	7.	184	000	1	1	10	77.0	0.	1	000	1	1
118	90.0	7.	185	000	1	1	10	77.0	0.	1	000	1	1
119	90.0	7.	186	000	1	1	10	77.0	0.	1	000	1	1
120	90.0	7.	187	000	1	1	10	77.0	0.	1	000	1	1
121	90.0	7.	188	000	1	1	10						

 PEAK OUTFLOW IS 487. AT TIME 2.42 HOURS *****

PEAK FLOW (CFS) 487.	TIME (HR) 2.42	6-HR 111. 2.371	MAXIMUM AVERAGE FLOW 24-HR 44. 2.272	15.58-HR 44. 2.272
		(INCHES) (AC-FT) 55.	61. 61.	61.
PEAK STORAGE (AC-FT) 108.	TIME (HR) 2.42	5-HR 98.	MAXIMUM AVERAGE STORAGE 24-HR 92.	15.58-HR 92.
PEAK STAGE (FEET) 411.85	TIME (HR) 2.42	5-HR 411.34	MAXIMUM AVERAGE STAGE 24-HR 411.03	16.58-HR 411.03

CUMULATIVE AREA = 0.50 SQ MI

TIME IN HOURS. AREA IN SQUARE MILES
CUBIC FEET PER SECOND
RUNOFF SUMMARY

OPERATION	STATION	PEAK FLOW	TIME OF PEAK	AVERAGE FLOW 6-HOUR	FLOW FOR MAXIMUM PERIOD 72-HOUR	BASEIN AREA	MAXIMUM STAGE	TIME OF MAX STAGE
HYDROGRAPH A)	A1	632.	2.06	142.	52.	0.50		
	A2	437.	2.42	111.	44.	0.50	411.85	2.42

SUMMARY OF DAM DRAINAGING/RELEASE ANALYSIS FOR STATION A2

PLAN 1

FLYNN
SUGAR
SUPPLY

INITIAL VALUE
410.30
77.
0.

SPILLWAY CREST
410.30
77.0.

411.10
93.
9.
JF DAM

1.00
JUL 1955

411-65
W.S. ELEV
RCSERVJIR
14X14UM

MAXIMUM
DEPTH:
OVER DAM
0.75

MAXIMUM
STORAGE
AC-FY
108.

487.

5.08
HUGH
OVER TOP
DUKATI 13N

TIME OF
MAX. OUTFLOW
HOURS 2.42

TIME OF FAILURE HOURS
0.0

◆◆◆ NORMAL END OF JJA ◆◆◆

APPENDIX 6

REFERENCES

LAKE KALMIA DAM

APPENDIX 6
REFERENCES

LAKE KALMIA DAM

Chow, Ven Te, Open Channel Hydraulics, McGraw Hill Book Company, New York, 1959.

King, H.W. and E.F. Brater, Handbook of Hydraulics, McGraw Hill Book Company, New York, Fifth Edition 1963.

Lewis, J.V. and H.B. Kummel (1910-1912) Geologic Map of New Jersey, revised by H.B. Kummel, 1931, and by M.E. Johnson, 1950. New Jersey Department of Conservation of Economic Development Atlas.

Schway, G.O., R.K. Frevert, T.W. Edmister, and K.K. Barnes, Soil and Water Conservation Engineering, The Ferguson Foundation Agricultural Engineering Series, John Wiley and Sons, Inc., New York, 1966, 683 pp.

U.S. Army Corps of Engineers, Hydrologic Engineering Center, Flood Hydrograph Package (HEC-1) Users Manual Preliminary, Davis, California, March 1981.

U.S. Department of Agriculture, Soil Conservation Service, Urban Hydrology for Small Watersheds, Technical Release No. 55, Washington, 1975.

U.S. Department of Commerce, Weather Bureau, "Seasonal Variation of the Probable Maximum Precipitation East of the 105th Meridian for Areas from 10 to 1000 Square Miles and Durations of 6, 12, 24, and 48 Hours", Hydrometeorological Report No. 33, Washington, 1977, 816 pp.

U.S. Department of Commerce, Weather Bureau, "Five to 60-minute Precipitation Frequency for the Eastern and Central United States", Hydrometeorological Report No. 35, Washington, 1977, 33pp.

U.S. Department of Interior, Bureau of Reclamation, Design of Small Dams, U.S. Government Printing Office, Washington, 1977, 816 pp.

U.S. Department of Interior, Geological Survey, 7.5-Minute Series (topographic) Maps, Scale 1:24,000, Contour Interval 20 Feet: Blairstown, N.J., (1954), Photorevised, 1971.

Viessman, Warren, Jr., J.W., Knapp, G.L. Lewis, T.E. Harbaugh, Introduction to Hydrology, Harper and Row, Publishers, New York, Second Edition 1977, 704 pp.

DATE
ILMED
-8